

Striping			
Location	Lt/Rt	78000200	78000600
		Thermoplastic Pavement Marking - Line, 4"	Thermoplastic Pavement Marking - Line, 6"
		FOOT	FOOT
STA 86+71.54 to STA 88+18.46	Lt	147	
STA 86+71.54 to STA 88+18.46	Rt	147	
STA 86+71.54 to STA 88+18.46	Lt	294	
STA 86+71.54 to STA 88+18.46	Rt	294	
STA 86+71.54 to STA 88+18.46	Lt/Rt		32
Total		882	32

Storm Sewer					
Location	Lt/Rt	55100700	55101100	550A0360	550A0400
		Storm Sewer Removal, 15"	Storm Sewer Removal, 21"	Storm Sewers, Class A, Type 2, 15"	Storm Sewers, Class A, Type 2, 21"
		FOOT	FOOT	FOOT	FOOT
STA 87+50	Rt	10		10	
STA 87+85	Rt	10		13	
STA 87+10	Lt		10		10
Total		20	10	23	10

Guardrail						
Location	Lt/Rt	63000001	LR631020	63100105	60900105	63200310
		Steel Plate Beam Guardrail, Type A, 6' Posts	Traffic Barrier Terminal, Type 1	Traffic Barrier Terminal, Type 10	Aluminum Railing, Type L	Guardrail Removal
		FOOT	FOOT	FOOT	FOOT	FOOT
STA 87+00 to STA 87+50	Rt	50	1	1		65
STA 87+45 to STA 87+58	Lt	20	1	1		30
STA 87+48 to STA 87+76	Rt				20	
STA 88+20 to STA 88+47	Lt				20	
Total		70	2	2	40	95

Landscaping/Erosion Control									
Location	Lt/Rt	21101625	25000110	25000300	X2511650	29000400	20101400	20101500	20101600
		Topsoil Furnish and Place, 6"	Seeding, Class 1A	Seeding, Class 3	Erosion Control Blanket (Special)	Perimeter Erosion Barrier	Nitrogen Fertilizer Nutrient	Phosphorous Fertilizer Nutrient	Potassium Fertilizer Nutrient
		SQ YD	ACRE	ACRE	SQ YD	FOOT	POUND	POUND	POUND
STA 86+71.54 to STA 87+50	Rt	210	0.04		210	20	3.6	3.6	3.6
STA 87+85 to STA 88+18.46	Rt	85	0.01	0.01	85	25	1.8	1.8	1.8
STA 86+71.54 to STA 87+20	Lt	275	0.06		275	5	5.4	5.4	5.4
STA 87+35 to STA 88+18.46	Lt	135	0.03		135	10	2.7	2.7	2.7
Total		705	0.14	0.01	705	60	13.5	13.5	13.5

Pavement											
Location	Lt/Rt	40603310	40603060	40600100	42400300	44000600	44000100	35101800	35101600	60605000	44000500
		Hot-Mix Asphalt Surface Course, Mix "D", NS0	Hot-Mix Asphalt Binder Course, IL-10.0, NE0	Bituminous Materials Prime Coat	Portland Cement Concrete Sidewalk, 5"	Sidewalk Removal	Pavement Removal	Aggregate Base Course, Type B, 6"	Aggregate Base Course, Type B, 4"	Combination Concrete Curb and Gutter, Type B6.24	Combination Curb and Gutter Removal
		TON	TON	GALLON	SQ FT	SQ FT	SQ YD	SQ YD	SQ YD	FOOT	FOOT
STA 86+71.54 to STA 87+32	Lt/Rt	20	65	35	190	190	215	115	311	75	75
STA 87+88 to STA 88+18.46	Lt/Rt	20	65	35	305	305	220	115	312	95	95
Total		40	130	70	495	495	435	230	623	170	170

FILE NAME :	USER NAME = #USER#	DESIGNED - D.R	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.D. RFE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#	PLOT SCALE = #SCALE#	DRAWN - G.R	REVISED -			2543	10-00045-00-BR	DuPAGE	16	4	
	PLOT DATE = #DATE#	CHECKED - J.B	REVISED -			CONTRACT NO. 63812					
		DATE -	REVISED -			SCALE:	STA. 86+71.54 TO STA. 88+18.46	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			