

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL	Wolf Road @ Winters Drive	CONSTRUCTION TYPE CODE: 0021		CONSTRUCTION TYPE CODE: 0021		CONSTRUCTION TYPE CODE: 0042	
					STP FUNDS 80 % FED 20% LOCAL		STP FUNDS 0 % FED 100% LOCAL		STP FUNDS 80 % FED 20% LOCAL	
* 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	130	130	130					
* 44000600	SIDEWALK REMOVAL	SQ FT	1856	1856	1856					
67100100	MOBILIZATION	L SUM	1	1	1					
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	1					
72000100	SIGN PANEL - TYPE 1	SQ FT	21	21	21					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	442	442	442					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	367	367	367					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	73	73	73					
78300100	PAVEMENT MARKING REMOVAL	SQ FT	348	348	348					
80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	1	1					
81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	690	690	690					
81028210	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2 1/2" DIA.	FOOT	113	113	113					
81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	108	108	108					
81028240	UNDERGROUND CONDUIT, GALVANIZED STEEL, 4" DIA.	FOOT	195	195	195					
81400100	HANDHOLE	EACH	4	4	4					
81400200	HEAVY-DUTY HANDHOLE	EACH	2	2	2					
81400300	DOUBLE HANDHOLE	EACH	1	1	1					
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1	1	1					
86200300	UNINTERRUPTABLE POWER SUPPLY, EXTENDED	EACH	1	1	1					
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	865	865	865					
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1091	1091	818		273			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1321	1321	1321					
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	418	418	418					
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	832	832	832					
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	121	121	121					
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	625	625	625					
87500600	TRAFFIC SIGNAL POST, 10 FT.	EACH	3	3	3					
87501200	TRAFFIC SIGNAL POST, 16 FT.	EACH	3	3	3					
87501400	TRAFFIC SIGNAL POST, 18 FT.	EACH	1	1	1					

* Speciality Items

PLAN SURVEYED BY DATE
 NOTE BOOK NO. OF MAY CHECKED
 NO. PAID FILE NAME
 CHRISTOPHER B. BURKE ENGINEERING LTD.
 8575 West Highway Road, Suite 600
 Rosemont, Illinois 60018
 (617) 925-5300