

# SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	URBAN TOTAL QUANTITY	STATE	COAL VALLEY	ROCK ISLAND
				0011 80% FED/ 20% STATE	0028 100%	0005 100%
54010505	PRECAST CONCRETE BOX CULVERTS 5'X5'	FOOT	25	25		
54215550	METAL END SECTION 15"	EACH	3	3		
54215553	METAL END SECTIOIN 18"	EACH	1	1		
54215565	METAL END SECTION 30"	EACH	2	2		
54215571	METAL END SECTION 36"	EACH	1	1		
54244405	<i>FLUSH INLET BOX FOR MEDIAN, STANDARD 542546</i>	<i>EACH</i>	<i>2</i>	<i>2</i>		
54248510	CONCRETE COLLAR	CUYD	1.34	1.34		
54260311	TRANSVERSABLE PIPE GRATES	FOOT	103.66	103.66		
54261436	CONCRETE END SECTION, STANDARD 542001, 36", 1:4	EACH	1	1		
54262430	CONCRETE END SECTION, STANDARD 542006, 30", 1:4	EACH	1	1		
542D0220	PIPE CULVERTS, CLASS D, TYPE 1, 15"	FOOT	230	230		
542D0235	PIPE CULVERTS, CLASS D, TYPE 1, 30"	FOOT	204	204		
542D1063	PIPE CULVERTS, CLASS D, TYPE 2, 18"	FOOT	60	60		
542D1081	PIPE CULVERTS, CLASS D, TYPE 2, 36"	FOOT	348	348		
56100500	WATER MAIN 4"	FOOT	640		640	
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1		1	
56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	1		1	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	112	112		
60100080	FRENCH DRAINS	CUYD	45	45		
60224469	MANHOLES, TYPE A, 9'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
60246805	<i>MEDIAN INLET (604106)</i>	<i>EACH</i>	<i>2</i>	<i>2</i>		
60255500	MANHOLES TO BE ADJUSTED	EACH	1		1	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3		3	
60260100	INLETS TO BE ADJUSTED	EACH	6			6
60600095	CLASS SI CONCRETE (OUTLET)	CUYD	1.1	1.1		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	121	121		

26

\*SPECIALTY ITEMS

FILE NAME * c:\pwork\pww\dot\work\asr\10285004-sht-schedule.dgn PLOT SCALE * 1/8"=1'-0" / 1/8"=1'-0" PLOT DATE * Fri Feb 01 10:26:41 2013	USER NAME * rankasr DESIGNED - DRAWN - CHECKED - DATE -	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION		SUMMARY OF QUANTITIES		F.A.U. RTE. 5786	SECTION 40BR	COUNTY Rock Island	TOTAL SHEETS 225	SHEET NO. 6
	SCALE: SHEET OF SHEETS STA. TO STA.							ILLINOIS FED. AID PROJECT			
								CONTRACT NO. 64341			

*Rev.*