SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	LOCATION		OFFSET
	US Rte 6		
13	RT	377+49.43	55.93'
13	RT	377+49.43	55.93'
11	LT	381+25.85	55.11'
9	RT	381+41.29	88.58'
9	RT	381+41.29	100.12'
9	RT	381+41.29	114.51'
15	RT	387+85.00	115.85
	Niabi Zoo Road		
6	LT	11+50.79	155.78'
84			

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	LOCATION		OFFSET
	US Rte 6		
24	RT	377+47.67	57.94'
24	RT	377+47.67	57.94'
24	RT	377+47.67	57.94'
26	RT	377+52.49	47.42'
18	RT	378+02.91	47.42'
	Niabi Zoo Road		
15	RT	11+79.15	135.10'
131			

20100500 TREE REMOVAL, ACRES

ACRES	LOCATION	
	US Rte 6	
0.75	RT	384+72.37 - 394+00.01
	Niabi Zoo Rd	
0.25	LT	15+66.34 - 16+09.58
0.25	LT	16+24.93 - 16+55.09
1.25		

25000400 NITROGEN FERTILIZER NUTRIENT

POUND	LOCATION	
	US Rte 6	
232.20	LT & RT	372+00.00 - 383+15.71
222.30	LT & RT	383+42.33 - 397+70.00
	Niabi Zoo Rd	
54.00	LT	10+50.00 - 19+81.02
88.20	RT	10+50.00 - 20+00.00
596.70		

25000500 PHOSPHORUS FERTILIZER NUTRIENT

POUND	LOCATION	
	US Rte 6	
232.20	LT & RT	372+00.00 - 383+15.71
222.30	LT & RT	383+42.33 - 397+70.00
	Niabi Zoo Rd	
54.00	LT	10+50.00 - 19+81.02
88.20	RT	10+50.00 - 20+00.00
596.70		

25000600 POTASSIUM FERTILIZER NUTRIENT

POUND	LOCATION	
	US Rte 6	
232.20	LT & RT	372+00.00 - 383+15.71
222.30	LT & RT	383+42.33 - 397+70.00
	Niabi Zoo Rd	
54.00	LT	10+50.00 - 19+81.02
88.20	RT	10+50.00 - 20+00.00
596.70		

20200100 EARTH EXCAVATION

CU YD	LOCATION	
	US Rte 6	
215	RT & LT	372+00.00 - 375+00.00
1,345	RT & LT	375+00.00 - 381+00.00
3,640	RT & LT	381+00.00 - 387+00.00
1,250	RT & LT	387+00.00 - 393+00.00
215	RT & LT	393+00.00 - 397+70.00
	Niabi Zoo Rd	
5,095	RT & LT	10+00.00 - 14+00.00
2,840	RT & LT	14+00.00 - 19+00.00
660	RT & LT	19+00.00 - 20+00.00
15,260		

20400800 FURNISHED EXCAVATION

CU YD	LOCATION	
	US Rte 6	
125	RT & LT	372+00.00 - 375+00.00
2,554	RT & LT	375+00.00 - 381+00.00
2,752	RT & LT	381+00.00 - 387+00.00
4,569	RT & LT	387+00.00 - 393+00.00
654	RT & LT	393+00.00 - 397+70.00
	Niabi Zoo Rd	
1,844	RT & LT	10+00.00 - 14+00.00
12,498		

21101615 TOPSOIL FURNISH AND PLACE, 4"

SQ YD	LOCATION	
	US Rte 6	
5,976	LT	372+00.00 - 382+64.46
5,791	RT	372+50.00 - 382+64.46
8,188	LT	384+14.96 - 397+70.00
2,676	RT	385+41.96 - 397+70.00
	Niabi Zoo Rd	
2,938	LT	10+50.00 - 19+80.08
5,365	RT	10+50.00 - 15+98.14
1,158	RT	16+21.99 - 20+00.00
32,092		

25000100 SEEDING, CLASS 1

ACRE	LOCATION	
	Niabi Zoo Rd	
0.50	RT	16+25.00 - 20+00.00
0.50		

FILE NAME = c:\pw_work\pwidot\renkesrw\dms36691\D2005584-sht-schedules.dgn	USER NAME = renkesrw	DESIGNED -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	DRAWN -	REVISED -
Default	PLOT DATE = Mon Feb 04 07:20:00 2013	CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5786	40BR	Rock Island	225	29
		CONTRACT NO. 64341		
	ILLINOIS FED. AID PROJECT			