SCHEDULE OF QUANTITIES

25000210 SEEDING, CLASS 2A

ACRE	LOCATION	
	US Rte 6	
2.50	LT & RT	370+35.00 - 383+15.71
2.00	LT & RT	383+42.33 - 397+70.00
	Niabi Zoo Rd	
0.50	LT	10+50.00 - 19+81.02
0.50	RT	10+50.00 - 20+00.00
5.50		

25000310 SEEDING, CLASS 4

ACRE	LOCATION	
	US Rte 6	
0.75	LT & RT	370+35.00 - 383+15.71
0.75	LT & RT	383+42.33 - 397+70.00
	Niabi Zoo Rd	
0.25	LT	10+50.00 - 19+81.02
0.50	RT	10+50.00 - 20+00.00
2.25		

25000750 MOWING

ACRE	LOCATION	
	US Rte 6	
3.00	LT & RT	372+00.00 - 383+15.71
2.75	LT & RT	383+42.33 - 397+70.00
	Niabi Zoo Rd	
0.75	LT	10+50.00 - 19+81.02
1.00	RT	10+50.00 - 20+00.00
7.50		

25100125 MULCH, METHOD 3

ACRE	LOCATION	
	US Rte 6	
3.00	LT & RT	372+00.00 - 383+15.05
2.75	LT & RT	383+50.55 - 397+70.00
	Niabi Zoo Rd	
0.75	LT	10+50.00 - 19+81.02
1.00	RT	10+50.00 - 20+00.00
7.50		

25100630 EROSION CONTROL BLANKET

SQ YD	LOCATION	
	US Rte 6	
1,542	LT	372+76.12 - 385+15.71
90	RT	375+00.65 - 376+00.65
408	RT	376+59.23 - 381+23.56
111	RT	381+72.98 - 383+14.82
2,452	LT	383+42.33 - 395+75.75
1,271	RT	385+65.77 - 394+27.02
	Niabi Zoo Rd	
246	LT	10+74.63 - 13+47.38
197	LT	16+39.42 - 18+76.77
89	RT	16+50.23 - 16+76.03
66	RT	17+17.46 - 17+78.95
28	RT	18+27.13 - 18+57.62
62	RT	19+08.65 - 19+55.55
6,560		

25100900 TURF REINFORCEMENT MAT

SQ YD	LOCATION		OFFSET	NOTE
	US Rte 6			
3.89	RT	385+68.09	81.85'	5' x 7'
3.89	RT	387+55.32	73.06'	5' x 7'
	Niabi Zoo Rd			
17.11	LT	15+85.57	35.75'	14' X 11'
24.89				

28000250 TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION	
	US Rte 6	
1,728	LT & RT	372+00.00 - 383+15.71
1,602	LT & RT	383+42.33 - 397+70.00
	Niabi Zoo Rd	
360	LT	10+50.00 - 19+81.02
588	RT	10+50.00 - 20+00.00
4,278		

28000305 TEMPORARY DITCH CHECKS

FOOT	LOCATION		NOTES
	US Rte 6		
132	LT	372+75.00 - 383+15.71	EVERY 100'
84	RT	376+58.49 - 383+15.71	EVERY 100'
156	LT	383+42.33 - 395+75.00	EVERY 100'
108	RT	385+75.00 - 394+25.00	EVERY 100'
	Niabi Zoo Rd		
36	LT	10+75.00 - 13+50.00	EVERY 100'
24	LT	16+75.00 - 18+75.00	EVERY 100'
540			

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION		NOTE
	US Rte 6		
275	RT	371+75.00 - 374+50.00	
131	LT	382+64.84 - 383+12.23	
133	LT	383+46.18 - 384+01.73	
125	RT	386+75.00 - 388+00.00	
350	RT	390+25.00 - 393+75.00	
	Niabi Zoo Rd		
472	RT	10+43.92 - 12+39.32	LT & RT OF STREAM
375	RT	12+25.00 - 16+00.00	
195	LT	13+50.00 - 15+45.18	
2,056			

28000500 INLET AND PIPE PROTECTION

EACH	LOCATION		OFFSET
	US Rte 6		
1	RT	376+00.00	48.21'
1	RT	381+25.03	89.71'
1	RT	385+69.99	80.32'
1	RT	387+54.80	75.27'
	Niabi Zoo Rd		
1	LT	15+85.57	35.75'
1	LT	16+39.69	33.08'
1	RT	16+50.23	49.71'
1	RT	17+36.54	37.96'
1	RT	19+13.62	32.86'
9			

FILE NAME = c:\pw_work\pwidot\renkesrw\dms36691\D2005584-sht-schedules.dgn	USER NAME = renkesrw	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = Mon Feb 04 07:20:33 2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5786	40BR	Rock Island	225	30
		CONTRACT NO. 64341		
	ILLINOIS FED. AID PROJECT			