

# SCHEDULE OF QUANTITIES

ITEM NO.	DESCRIPTION	EACH	LOCATION	OFFSET	NOTE
54262430	CONCRETE END SECTION, STANDARD 542006, 30", 1:4				
		<u>1</u>	Niabi Zoo Rd LT	20.94'	Double Pipe
		1			
542D0220	PIPE CULVERTS, CLASS D, TYPE 1, 15"				
		<u>50</u>	US Rte 6 RT	50'	
		110	Niabi Zoo Rd RT		376+04.56 - 376+54.55
		<u>144</u>	RT		16+56.96 - 17+66.43
		304			17+66.43 - 19+09.88
542D0235	PIPE CULVERTS, CLASS D, TYPE 1, 30"				
		<u>172</u>	Niabi Zoo Rd LT & RT		15+82.05
		<u>32</u>	LT		20.94' LT - 64.24' RT - DOUBLE PIPE
		204			36.14' LT - 33.82' LT
542D1063	PIPE CULVERTS, CLASS D, TYPE 2, 18"				
		<u>80</u>	Niabi Zoo Rd RT		15+82 - 16+56.96
		80			
542D1081	PIPE CULVERTS, CLASS D, TYPE 2, 36"				
		<u>190</u>	US Rte 6 RT		381+28.70 - 383+14.19
		<u>158</u>	Niabi Zoo Rd LT & RT		10+80.32
		348			68.71' LT - 88.37' RT
56100500	WATER MAIN 4"				
		<u>640</u>	US Rte 6 RT		375+00.00 - 381+25.00
		640			52' - 72'
56400300	FIRE HYDRANT TO BE ADJUSTED				
		<u>1</u>	Niabi Zoo Rd RT		18+60.83
		1			50.77'
56400400	FIRE HYDRANT TO BE RELOCATED				
		<u>1</u>	US RTE 6 RT		381+25.00
		1			80' EX RT STA 382+00

ITEM NO.	DESCRIPTION	CU YD	LOCATION	OFFSET
60100080	FRENCH DRAINS			
		<u>1</u>	US Rte 6 LT	
		2	RT	
		<u>1</u>	LT	
		2	RT	
		<u>1</u>	LT	
		3	RT	
		<u>2</u>	LT	
		3	RT	
		<u>2</u>	LT	
		1	RT	
		<u>1</u>	LT	
		1	RT	
		<u>1</u>	LT	
		1	RT	
		<u>1</u>	LT	
		1	RT	
		<u>1</u>	Niabi Zoo Rd LT	
		3	RT	
		<u>2</u>	LT	
		3	RT	
		<u>2</u>	LT	
		2	RT	
		<u>2</u>	LT	
		2	RT	
		<u>1</u>	RT	
		45		
60224469	MANHOLES, TYPE A, 9'-DIAMETER, TYPE 1 FRAME, CLOSED LID			
		<u>1</u>	Niabi Zoo Rd RT	67.79'
		1		15+85.57
60246805	MEDIAN INLET (604106)			
		<u>1</u>	NIABI ZOO ROAD RT	
		1		16+56.96
		<u>2</u>	RT	17+66.43
60255500	MANHOLES TO BE ADJUSTED			
		<u>1</u>	US Rte 6 LT	43.74
		1		374+00.00
60257900	MANHOLES TO BE RECONSTRUCTED			
		<u>1</u>	US Rte 6 LT	39.54'
		1	LT	36.03'
		<u>1</u>	RT	36.87'
		2		378+00.09
				382+20.54
				382+25.83