SCHEDULE OF QUANTITIES

78009012 MODIFIED URETHANE PAVEMENT MARKING - LINE 12"

FOOT	LOCATION		NOTE
	US Rte 6		
388	LT & RT	376+16.62 - 384+40.67	MEDIAN, DIAGONALS - YELLOW
162	LT & RT	388+57.39 - 393+30.73	MEDIAN, DIAGONALS - YELLOW
	Niabi Zoo Rd		
70	RT	10+31.41 - 13+19.88	MEDIAN, DIAGONALS - YELLOW
80	LT	10+18.70 - 10+57.63	ISLAND, DIAGONALS - WHITE
700			

78009024 MODIFIED URETHANE PAVEMENT MARKING - LINE 24"

FOOT	LOCATION		NOTE
	Niabi Zoo Rd		
16	LT	10+32.57	STOP BAR - WHITE
18	LT	10+44.34	STOP BAR - WHITE
13	RT	16+16.88	STOP BAR - WHITE (78TH AVE)
47			

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION		NOTE
	US Rte 6		
3	CL	374+13.75 - 374+93.60	TWO-WAY AMBER
38	LT & RT	375+33.68 - 382+53.61	TWO-WAY AMBER
7	RT	381+37.57 - 382+58.20	ONE-WAY CRYSTAL
5	LT & RT	384+16.35 - 384+44.31	TWO-WAY AMBER
2	RT	384+17.67 - 384+37.91	ONE-WAY CRYSTAL
14	LT	385+30.25 - 387+90.43	ONE-WAY CRYSTAL
59	LT & RT	385+25.08 - 393+95.25	TWO-WAY AMBER
	Niabi Zoo Rd		
17	LT & RT	10+31.41 - 13+59.92	TWO-WAY AMBER
10	CL	14+00.00 - 19+81.00	TWO-WAY AMBER
155			

78201000 TERMINAL MARKER - DIRECT APPLIED

EACH	LOCATION	
	US Rte 6	
1	LT	385+19.51
1		

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION	
	US Rte 6	
2	LT	383+97.79 - 385+12.69
2		

78200520 BARRIER WALL MARKERS, TYPE B

EACH	LOCATION	
	US Rte 6	
2	LT	382+64.29 - 383+97.79
3	RT	382+64.29 - 384+15.29
5		

78300100 PAVEMENT MARKING REMOVAL

SQ FT	LOCATION		NOTE
	US Rte 6		
905	LT	370+45.55 - 397+60.41	WESTBOUND EDGE OF PAVEMENT
226	CL	370+46.98 - 397+60.24	CENTERLINE SKIP DASH
118	RT	370+45.00 - 374+00.00	EASTBOUND EOP
118	RT	394+05.08 - 397+60.08	EASTBOUND EOP
	Niabi Zoo Rd		
399	CL	16+10.17 - 22+08.74	CENTERLINE DOUBLE YELLOW
1,766			

X0326805 FOUNDATION REMOVAL

SQ FT	LOCATION		OFFSET	
	US Rte 6			
6	RT	377+10.54	67.44'	CONCRETE SIGN - 12' HIGH
6				

X7240300 SIGN REMOVAL

EACH	LOCATION		OFFSET	
	US Rte 6			
1	RT	384+69.00	70'	NAIBI ZOO SIGNS
1				

X7810010 REFLECTOR MARKERS, TYPE B

EACH	LOCATION	
	US Rte 6	
4	LT&RT	381+81.28 - 383+98.38
4		

Z0025505 PROPERTY MARKERS

EACH	LOCATION	
	US Rte 6	
1	RT	377+45.83
1	RT	381+30.48
2		

Z0005300 BOX CULVERT TO BE CLEANED

EACH	LOCATION		OFFSET
1	LT & RT	387+55.19	60' X 5' X 5'
1			

FILE NAME = c:\pw_work\pwidot\renkesrw\dms36691\D2055584-sht-schedules.dgn	USER NAME = renkesrw	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = Mon Feb 04 07:25:19 2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. | TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
5786	40BR	Rock Island	225	37
		CONTRACT NO. 64341		
	ILLINOIS FED. AID PROJECT			