

BITUMINOUS SCHEDULE

LOCATION	REMARKS	44000155	44004250	44213200	48101500	48203019	48203021	X4400110	X4401198	Z0062456	Z0065200
		HMA SURFACE REMOVAL 1.5"	PAVED SHOULDER REMOVAL	SAW CUTS	AGGREGATE SHOULDERS, TYPE B 6"	HMA SHOULDERS, 5 1/2"	HMA SHOULDERS, 6"	TEMPORARY PAVEMENT REMOVAL	HMA SURFACE REMOVAL, VAR DEPTH	TEMPORARY PAVEMENT	SHOT ROCK
		SQ YD	SQ YD	FOOT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON
US Rte 6											
LT											
370+35.00 - 374+00.00	11' SHLDR (8' FINAL)		446.1	365.0		446.11					
374+00.00 - 383+14.96	11' SHLDR (TEMP PAV)		813.3	915.0				1118.28		1118.28	
374+00.00 - 382+00.00	8' SHLDR (FINAL)					711.11					
383+64.66 - 394+05.08	11' SHLDR (TEMP PAV)		924.8	1040.4				1271.62		1271.62	
385+02.41 - 394+05.08	8' SHLDR (FINAL)					802					
394+05.08 - 397+70.00	11' SHLDR (8' FINAL)		446	364.9		446					
RT											
370+60.00 - 371+07.39	12' SHLDR (8' FINAL)		63	47.4		63					
371+96.72 - 374+00.00	12' SHLDR (8' FINAL)		271	203.3		271					
374+00.00 - 379+81.75	12' SHLDR (8' FINAL)		1034	581.8		776					
374+85.80 - 376+12.00	10' BIKE PATH										
376+46.11 - 381+41.07	10' BIKE PATH										
379+81.75 - 382+00.00	4' SHLDR		194	218.3		97					
385+02.41 - 394+05.08	15' SHLDR (8' FINAL)		1504	902.7		1504					
394+04.94 - 397+70.00	15' SHLDR (8' FINAL)		608	365.1		608					
CL											
374+00.00 - 375+00.00	2 - 12' THRU							267			
375+00.00 - 375+73.68	2 - 12' THRU							196			
375+73.68 - 380+00.00	2 - 12' THRU, 14' & VAR MEDIAN							604			
380+00.00 - 381+38.68	2 - 12' THRU, 14' & VAR MEDIAN, 12' & VAR TURN										
381+38.68 - 382+00.00	2 - 12' THRU, 14' MEDIAN, 12' RIGHT TURN										
385+02.41 - 387+90.08	2 - 12' THRU, 12' LEFT TURN										
387+90.08 - 394+05.08	2 - 12' THRU, 2' - 14' & VAR MEDIAN							1080			
Niabi Zoo Rd											
Reconstruction											
10+19.00 - 13+19.88	2 - 12' THRU, VAR MEDIAN, 10' BIKE PATH				67		267				3198
13+19.88 - 15+75.00	2 - 12' THRU, 10' BIKE PATH				57		227				2712
15+75.00 - 18+37.00	2 - 12' THRU				116		233				
18+37.00 - 19+75.00	2 - 12' THRU				31		61				
19+75.00 - 19+81.01	2 - 12' THRU										
Resurfacing											
10+31.00	LT & RT										
10+31.00 - 17+25.00	RT (Inc Surf Spl 5.5' - 8.0')										
10+31.00 - 31+00.00	LT & RT (Surf Removal 24')	5134.0									
10+31.00 - 63+40.00	LT & RT										
17+25.00 - 21+45.00	RT (Inc Surf Spl 5')										
21+45.00 - 23+95.00	RT (Surf Removal 5')	139.0									
23+95.00 - 31+00.00	RT										
23+95.00 - 41+30.00	RT (Inc Surf Spl 5')										
31+00.00 - 41+30.00	RT										
31+00.00 - 63+40.00	LT & RT (Surf Removal 22')	7920.0									
31+50.00 - 33+40.00	LT (Inc Surf Spl 5')										
33+60.00 - 34+00.00	LT STA (Surf Removal 5')	22.2									
34+00.00	MB TO LT 34+00										
34+20.00 - 35+80.00	LT (Inc Surf Spl 5')										
35+20.00 - 35+60.00	LT STA (Surf Removal 5')	22.2									
35+60.00	MB TO LT 35+60										
36+10.00 - 37+00.00	LT (Inc Surf Spl 5')										
53+40.00 - 54+00.00	LT STA (Surf Removal 5')	33.3									
54+00.00	MB TO LT 54+00										
54+20.00 - 54+80.00	LT (Inc Surf Spl 5')										
55+10.00 - 55+70.00	LT (Inc Surf Spl 5')										
61+50.00	ENT/MB TO LT 61+50										
63+40.00	LT & RT										
ENTRANCES											
US RTE 6											
RT 374+68.00	CE 35'										
RT 376+29.00	CE 35'										
RT 381+41.07 - 382+25.00	DRIVEWAY/PARKING LOT										
RT 382+25.00 - 383+03.61	PARKING LOT (AS NEEDED)										
NIABI ZOO ROAD											
Reconstruction											
LT 15+47.23	FE 24'										
LT 16+20.07	PE 12'										
LT 19+00.00	FE 24'										
Resurfacing											
RT 40+10.00	PE										
LT 54+90.00	PE (Surf Removal 5')	13.9									
LT 55+25.00	PE										
LT 55+90.00	PE (Surf Removal 5')	13.9									
RT 57+30.00	PE										
LT 61+50.00	PE/MB (Surf Removal 5')	30.5									
RT 62+50.00	PE (Surf Removal 5')	50.0									
	Total	13379	6306	5003.70	271	5725	788	2390	2147	2390	5910