


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ACF		ACBRF	
				CONST. CODE 80% FED 20% STATE ROADWAY 0004	CONST. CODE 80% FED 20% STATE BRIDGE 0011 S.N. 098-0015		
30300011	AGGREGATE SUBGRADE IMPROVEMENT	TON	793	793			
30300104	AGGREGATE SUBGRADE IMPROVEMENT 4"	SQ YD	532	532			
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	1,909	1,909			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2			
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	122	122			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,576	1,576			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	140	140			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	346	346			
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	194	194			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4,780	4,780			
44000100	PAVEMENT REMOVAL	SQ YD	112	112			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,642	2,642			
44000600	SIDEWALK REMOVAL	SQ FT	938	938			
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,765	1,765			
44200094	PAVEMENT PATCHING, TYPE II, 8 INCH	SQ YD	191	191			

15  
+ SPECIALTY ITEM

FILE NAME \* SA10145388-EPPRCHV1825V6-44-SN10284C17-A1-5001.dgn



USER NAME * vaneason	DESIGNED - VLF	REVISED -
PLOT SCALE * 20,0000 ' / IN.	DRAWN - DJW	REVISED -
PLOT DATE * 10/12/2012	CHECKED - MAG	REVISED -
	DATE - 10-12-12	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: N/A	SHEET 2	OF 7 SHEETS	STA. TO STA.

F.A.P. RTE. 646	SECTION 101 BR-3	COUNTY WHITESIDE	TOTAL SHEETS 113	SHEET NO. 6
CONTRACT NO. 64C17				
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				