

40603085 HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70

TON	LOCATION	QUANTITY
	IL 40	
	STA. 629+40.00 TO 631+65.99 LT	245.50
	STA. 629+40.00 TO 632+47.68 RT	376.65
	STA. 632+85.09 TO 636+45.00 LT	440.25
	STA. 633+46.20 TO 636+45.00 RT	513.21
TOTAL:		1576.00 TON

40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50

TON	LOCATION	AREA (SQ YD)	DEPTH (IN)	QUANTITY
	IL 40			
	STA. 628+50.00 TO 631+35.59 LT	312.50	1.50	26.25
	STA. 632+54.30 TO 637+00.00 LT	550.04	1.50	46.20
	STA. 628+50.00 TO 632+75.33 RT	524.62	1.50	44.07
	STA. 634+78.63 TO 637+00.00 RT	277.23	1.50	23.29
TOTAL:		140.00		TON

40603340 HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70

TON	LOCATION	AREA (SQ YD)	DEPTH (IN)	QUANTITY
	IL 40			
	STA. 628+50.00 STA. 631+65.99 LT	785.80	1.50	66.01
	STA. 632+85.09 STA. 637+00.00 LT	1049.60	1.50	88.17
	STA. 628+50.00 STA. 632+05.06 RT	1003.65	1.50	84.31
	STA. 633+57.13 STA. 637+00.00 RT	1269.02	1.50	106.60
TOTAL:		346.00		TON

42001430 BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)

SQ YD	LOCATION	AVE WIDTH (FT)	QUANTITY
	IL 40		
	STA. 631+79.22 TO 631+91.45	142.66	96.93
	STA. 633+28.72 TO 633+40.95	142.66	96.93
TOTAL:			194.00 SQ YD

42400200 PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH

SQ FT	LOCATION	AVE WIDTH (FT)	QUANTITY
	IL 40		
	STA. 200+00.00 TO 204+78.00	10.00	4780.00
TOTAL:			4780.00 SQ FT

44000100 PAVEMENT REMOVAL

FOOT	LOCATION	QUANTITY
	IL 40	
	STA. 628+50.00 TO 631+00.00 LT	55.56
	STA. 628+50.00 TO 631+00.00 RT	55.56
TOTAL:		112.00 SQ YD

44004250 PAVED SHOULDER REMOVAL

SQ YD	LOCATION	QUANTITY
	IL 40	
	STA. 62850 TO 63160 LT	345
	STA. 62850 TO 63302 RT	503
	STA. 632+17.00 TO 637+00.00 LT	537
	STA. 633+58.00 TO 637+00.00 RT	380
TOTAL:		1765.00 SQ YD

44200094 PAVEMENT PATCHING, TYPE II, 8"

FOOT	LOCATION	QUANTITY
	IL 40	
	STA. 626+70.00 TO 643+82.00 LT	+10.00 1902.22
		10% 190.22
TOTAL:		191.00 SQ YD

44000500 COMBINATION CONCRETE CURB AND GUTTER REMOVAL

FOOT	LOCATION	QUANTITY
	IL 40	
	STA. 623+38.50 TO 632+43.09	1785.01
	STA. 632+72.35 TO 636+70.10	774.37
	STA. 637+60.92 TO 641+71.93	81.90
TOTAL:		2642.00 FOOT

44000600 SIDEWALK REMOVAL

SQ FT	LOCATION	WIDTH (FT)	QUANTITY
	IL 40		
	STA. 200+15.52 TO 200+81.06	6.00	393.24
	STA. 202+77.73 TO 203+68.39	6.00	543.96
TOTAL:			938.00 SQ FT

44300200 STRIP REFLECTIVE CRACK CONTROL TREATMENT

FOOT	LOCATION	QUANTITY
	IL 40	
	STA. 628+50.00 TO 637+00.00	325.00
TOTAL:		325.00 FOOT

48203023 HOT-MIX ASPHALT SHOULDERS, 6 1/2"

SQ YD	LOCATION	QUANTITY
	IL 40	
	STA. 628+50.00 TO 631+35.59 LT	312.50
	STA. 632+54.30 TO 637+00.00 LT	550.04
	STA. 628+50.00 TO 632+75.33 RT	524.62
	STA. 634+78.63 TO 637+00.00 RT	277.23
TOTAL:		1665.00 SQ YD

50901720 BICYCLE RAILING

FOOT	LOCATION	QUANTITY
	IL 40	
	STA. 200+00.00 TO STA. 204+00.00	400.00
TOTAL:		400.00 FOOT

60206100 INLETS TO BE ADJUSTED

EACH	LOCATION	OFFSET (FT)	QUANTITY
	IL 40		
	STA. 624+08.08	0.66	2.00
	STA. 627+08.28	0.66	2.00
TOTAL:			4.00 EACH

60610400 COMBINATION CURB AND GUTTER, TYPE M-6.24

FOOT	LOCATION	QUANTITY
	IL 40	
	STA. 623+44.82 TO 631+81.77 LT	837.67
	STA. 633+19.04 TO 634+25.51 LT	106.47
	STA. 637+72.14 TO 639+90.96 LT	219.36
	STA. 623+44.78 TO 632+13.73 RT	869.47
	STA. 633+43.01 TO 634+25.56 RT	82.73
	STA. 637+71.99 TO 639+91.02 RT	129.30
TOTAL:		2245.00 FOOT

60618300 CONCRETE MEDIAN SURFACE, 4 INCH

SQ FT	LOCATION	QUANTITY
	IL 40	
	STA. 631+82.81 TO STA. 631+91.45	251.43
	STA. 633+15.49 TO STA. 634+25.50	938.70
	STA. 637+72.05 TO STA. 639+91.00	2809.38
TOTAL:		4000.00 SQ FT

60623200 CONCRETE MEDIAN, TYPE SM-6.24

SQ FT	LOCATION	QUANTITY
	IL 40	
	STA. 623+35.85 TO STA. 623+44.80	72.41
	STA. 634+25.50 TO STA. 636+80.10	2564.70
	STA. 637+62.05 TO STA. 637+72.05	85.99
	STA. 639+91.00 TO STA. 641+71.93	1745.23
TOTAL:		4469.00 SQ FT

63100045 TRAFFIC BARRIER TERMINAL, TYPE 2

EACH	LOCATION	QUANTITY
	IL 40	
	STA. 630+74.38 TO 631+00.23	1.00
	STA. 634+99.92 TO 635+34.27	1.00
TOTAL:		2.00 EACH

63100070 TRAFFIC BARRIER TERMINAL, TYPE 5

EACH	LOCATION	QUANTITY
	IL 40	
	STA. 631+00.23 TO 631+30.02	1.00
	STA. 634+78.63 TO 634+99.92	1.00
TOTAL:		2.00 EACH

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6

EACH	LOCATION	QUANTITY
	IL 40	
	STA. 632+39.83 TO 632+95.48	1.00
	STA. 632+42.90 TO 632+98.55	1.00
TOTAL:		2.00 EACH

63100169 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED

EACH	LOCATION	QUANTITY
	IL 40	
	STA. 632+02.38 TO 632+39.83	1.00
	STA. 632+98.55 TO 633+36.03	1.00
TOTAL:		2.00 EACH

FILE NAME = S:\JUL16300-6399\6346\025\Microa\Sh\AD264C17-ah-t-schedule1.dgn



USER NAME = vanessam	DESIGNED - VLF	REVISED -
	DRAWN - DJW	REVISED -
PLOT SCALE = 40.0000' / IN.	CHECKED - MAG	REVISED -
PLOT DATE = 10/15/2012	DATE - 10-12-12	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET 2 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646	101 BR-3	WHITESIDE	113	18
CONTRACT NO. 64C17			FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT	