

# STRIPING SCHEDULE – W.B.

STRIPING SCHEDULE																				
LOCATION			78009004		78009006	7800908	78009012		70300100											
STATION TO STATION			REMARKS		LENGTH FT	MODIFIED URETHANE PAVEMENT MARKING – LINE 4"		MODIFIED URETHANE PAVEMENT MARKING – LINE 6"	MODIFIED URETHANE PAVEMENT MARKING – LINE 8"	MODIFIED URETHANE PAVEMENT MARKING – LINE 12"	MODIFIED URETHANE PAVEMENT MARKING – LINE 12"	SHORT TERM APP. Rate	SHORT-TERM PAVEMENT MARKING Note Center line short term will be placed like permenate pavement marking							
						EDGE LINES		CL	CHEVRON		DIAGONAL	PHASE		White	Yellow	White				
						White	Yellow	White	White	White	White		1	2	FOOT	DIAGONALS	DIAGONALS			
						FOOT	FOOT	FOOT	FOOT	FOOT	FOOT				FOOT	FOOT	FOOT			
WEST BOUND MAINLINE			HENRY COUNTY																	
571	+	32.09	TO	573	+	32.09	ENTRANCE RAMP		200.00	200			400			2		1,200		16
573	+	32.09	TO	574	+	21.04	ENTRANCE RAMP		88.95	89			180			2		538		8
574	+	21.04	TO	585	+	58.44	MAINLINE		1,137.40	1,137	1,137	290			2			580	96	96
585	+	58.44	TO	599	+	64.94	MAINLINE		1,406.50		1,407	360			2			720	120	120
585	+	58.44	TO	591	+	9.59	EXIT RAMP		551.15	1,110					157	2		2,533		48
591	+	9.59	TO	593	+	65.99	EXIT RAMP		256.40	256			520	95		2		1,743		24
593	+	65.99	TO	599	+	64.94	EXIT RAMP		598.95	599			150			2		1,498		48
SUB TOTAL EAST BOUND			HENRY COUNTY																	
						35,715	34,515	9,080	2,430	468	241			0	0			34,628	2,788	3,020
						63,126	58,136	15,285	6,919	585	128			1,795	1,960			74,443	4,788	5,348
						70,827	69,364	18,060	4,598	760	288			0	0			65,439	5,580	5,844
						133,953	127,500	33,345	11,517	1,345	416	0		1,795	1,960			139,882	10,368	11,192
						261,453		33,345	11,517	1,761				3,755				161,442		

\* 74/280 & 80  
 \*\* (81-2, 81-3, 37-1, 37-2-1) RS-1 & 81-3BR  
 \*\*\* ROCK ISLAND/HENRY COUNTY