

SUMMARY OF QUANTITIES

0040

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE
28200200	FILTER FABRIC	SQ YD	103	103
28500400	ARTICULATED BLOCK REVETMENT MAT	SQ YD	100	100
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	2,650.0	2,650.0
35101400	AGGREGATE BASE COURSE, TYPE B	TON	449	449
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	301	301
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	260	260
40600990	TEMPORARY RAMP	SQ YD	29	29
40603310	HOT- MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	316	316
40603335	HOT- MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	388	388
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	12	12
44201359	CLASS C PATCHES, TYPE IV, 10 INCH	SQ YD	174	174
48203019	HOT- MIX ASPHALT SHOULDERS, 5 1/2"	SQ YD	2,256	2,256
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6,460	6,460
50800515	BAR SPLICERS	EACH	27	27
51500100	NAME PLATES	EACH	2	2
54001001	BOX CULVERT END SECTIONS, CULVERT NO.1	EACH	1	1

* SPECIALTY ITEM
 *** NON- PARTICIPATING 100%

FILE NAME : c:\pwworkspace\pwworkspace\dossdd\0233029\02014	USER NAME : dossdd	DESIGNED : -	REVISED : -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES IL 84	F.A.P. RTE. 570	SECTION IGIT	COUNTY JO DAVIESS	TOTAL SHEETS 64	SHEET NO. 6	CONTRACT NO. 64F75
PLOT SCALE : 100.0000 / in. PLOT DATE : Tue Jan 22 11:30:16 2013				DRAWN : CHECKED : DATE :		SCALE: SHEET OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			