

SUMMARY OF QUANTITIES

0040

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE
54001002	BOX CULVERT END SECTIONS, CULVERT NO.2	EACH	1	1
54003000	CONCRETE BOX CULVERTS	CU YD	46.1	46.1
54010503	PRECAST CONCRETE BOX CULVERTS 5' X 3'	FOOT	60	60
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	94	94
5421D036	PIPE CULVERTS, CLASS D, TYPE 1 36" (TEMPORARY)	FOOT	20	20
5421D048	PIPE CULVERTS, CLASS D, TYPE 1 48" (TEMPORARY)	FOOT	20	20
54213450	END SECTIONS 15"	EACH	4	4
54215408	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 8"	EACH	1	1
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	6	6
60100915	PIPE DRAINS 6"	FOOT	59	59
60107600	PIPE UNDERDRAINS 4"	FOOT	355	355
61100500	EXPLORATION TRENCH 52" DEPTH	FOOT	100	100
61101009	STORM SEWERS PROTECTED, CLASS A, 8"	FOOT	100	100
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	4	4
63200310	GUARDRAIL REMOVAL	FOOT	767	767
63500105	DELINEATORS	EACH	8	8
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	30	30
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2

* SPECIALTY ITEM
 *** NON-PARTICIPATING 100%

FILE NAME * c:\pwworkspace\10000000\d0233029\02014	USER NAME * dosadd 0-shi-500.dgn	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES IL 84	F.A.P. RTE. 570	SECTION 101T	COUNTY JO DAVIESS	TOTAL SHEETS 64	SHEET NO. 7
PLOT SCALE * 1/8"=1'-0" / in. PLOT DATE * Tue Jan 22 11:30:26 2013				SCALE: SHEET OF SHEETS STA. TO STA.		CONTRACT NO. 64F75 ILLINOIS FED. AID PROJECT				