

CODE NO.	ITEM	UNIT	CONSTR. CODE
			STATE FUNDS 100% STATE ROADWAY 0044 RURAL
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2097
28200200	FILTER FABRIC	SQ YD	224
30300124	AGGREGATE SUBGRADE ^{IMPROVEMENT} 24"	SQ YD	2097
42000506	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4" (JOINTED)	SQ YD	3025
42001200	PAVEMENT FABRIC	SQ YD	3025
42100305	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 10 1/4"	SQ YD	121
42100615	PAVEMENT REINFORCEMENT	SQ YD	121
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2276
42400800	DETECTABLE WARNINGS	SQ FT	226
44000100	PAVEMENT REMOVAL	SQ YD	3146
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	211
44000600	SIDEWALK REMOVAL	SQ FT	2450
550A0050	STORM SEWER, CLASS A, TYPE 1, 12"	FOOT	30
55100500	STORM SEWER REMOVAL 12"	FOOT	37
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	20
60107600	PIPE UNDRDRAINS 4"	FOOT	155
60607500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24 (ABUTTING EXISTING PAVEMENT)	FOOT	211
67100100	MOBILIZATION	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
X0326340	PIPE UNDERDRAIN BACKFILL, SPECIAL	TON	160
X6040205	FRAME AND LIDS, SPECIAL	EACH	15
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	2
Z0018900	DRILL AND GROUT DOWEL BARS	EACH	212
Z0018911	DRILL AND GROUT #6 TIE BARS	EACH	92