

CODE NO.	ITEM	UNIT	CONSTR. CODE
			STATE FUNDS
			100% STATE
			ROADWAY
			0014
			RURAL
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1
70106700	TEMPORARY RUMBLE STRIPS	EACH	6
70400100	TEMPORARY CONCRETE BARRIER	FOOT	440
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	440
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1568
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	196
78100300	REPLACEMENT REFLECTOR	EACH	10
78300100	PAVEMENT MARKING REMOVAL	SQ FT	615
X0550300	SLOPE WALL BREAKING	SQ YD	253
X2810108	STONE RIPRAP, CLASS A4 (SPECIAL)	SQ YD	253
Z0001495	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	45
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	20
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	10
Z0001905	STRUCTURAL STEEL REPAIR	POUND	180
<u>Z0048665</u>	<u>RAILROAD PROTECTIVE LIABILITY INSURANCE</u>	<u>L SUM</u>	<u>1</u>

\* SPECIALITY ITEM

Rev. 4-15-13

Rev.