



BENCHMARKS

POINT	NORTH	EAST	ELEVATION	CHAIN	STATION	OFFSET	DESCRIPTION
CSL1	1471092.1535	2309589.8185	695.60	EXCL116	395+50.00	20.70 LT	CHISELED "C" IN TOP OF N. HEADWALL OF CROSSROAD CULV
DAS1	1471041.6548	2309859.4698	687.42	EXCL116	398+20.00	27.90 RT	CHISELED "C" SW. COR. WINGWALL BRDGE OVER DYKEMEN CRK
RFS1	1471092.4399	2310202.8344	697.42	EXCL116	401+63.00	25.3 LT	CHISELED "C" IN TOP OF E. HEADWALL UNDER FIELD ENT

NOTE:
ALL STATION OFFSETS ARE REFERENCED TO THE CENTERLINE OF IL ROUTE 116

HORIZONTAL CONTROL POINTS

POINT	NORTH	EAST	ELEVATION	CHAIN	STATION	OFFSET	DESCRIPTION
1001	1471051.6209	2310214.5210	697.91	EXCL116	401+74.97	15.44 RT	SET PIN & CAP FOR WORK POINT TOPO SURVEY POINT
1002	1471052.8716	2309902.8789	690.69	EXCL116	398+63.33	16.38 RT	SET PIN & CAP FOR WORK POINT TOPO SURVEY POINT
1003	1471087.7318	2309740.9780	691.71	EXCL116	397+01.19	17.34 LT	SET PIN & CAP FOR WORK POINT TOPO SURVEY POINT
1004	1471054.3705	2309521.6559	697.72	EXCL116	394+82.10	17.56 RT	SET PIN & CAP FOR WORK POINT TOPO SURVEY POINT
1006	1471073.7780	2309259.4210	N/A	EXCL116	392+19.74	CENTERLINE	SET MAG NAIL AT CENTERLINE OF PAVEMENT
1007	1471065.7280	2310403.3910	N/A	EXCL116	403+63.74	CENTERLINE	SET MAG NAIL AT CENTERLINE OF PAVEMENT



USER NAME = *USER*	DESIGNED - RWK	REVISED -
PLOT SCALE = *SCALE*	DRAWN - RWK	REVISED -
PLOT DATE = *DATE*	CHECKED - ST	REVISED -
	DATE - 9/2012	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ALIGNMENT, TIES, AND BENCHMARKS
IL ROUTE 116**

SCALE: 1"=50' SHEET NO. 1 OF 1 SHEETS STA. 392+19.74 TO STA. 403+63.74

F.A.P. RTE. 665	SECTION (144-B-1)BR	COUNTY FULTON	TOTAL SHEETS 48	SHEET NO. 12
				CONTRACT NO. 68778
ILLINOIS FED. AID PROJECT				