

SUMMARY OF QUANTITIES

LOCATION OF WORK: FAP ROUTE 840 (IL 49)
VERMILION COUNTY
S.N. 092-0171 - STA 211+11.00
STA. 209+07.70 to 212+85.71
RURAL

FUNDING BREAKOUT: 80% FEDERAL
20% STATE

CONSTRUCTION TYPE CODE: **M233**
0014

LOCATION OF WORK: FAP ROUTE 840 (IL 49)
VERMILION COUNTY
S.N. 092-0171 - STA 211+11.00
STA. 209+07.70 to 212+85.71
RURAL

FUNDING BREAKOUT: 80% FEDERAL
20% STATE

CONSTRUCTION TYPE CODE: **M233**
0014

CODE NO	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	60
20400800	FURNISHED EXCAVATION	CU YD	125
* 25000210	SEEDING, CLASS 2A	ACRE	0.25
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27
* 25100115	MULCH, METHOD 2	ACRE	0.25
* 25100630	EROSION CONTROL BLANKET	SQ YD	1083
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	30
28000305	TEMPORARY DITCH CHECKS	FOOT	40
28100109	STONE RIPRAP, CLASS A5	SQ YD	609
28200200	FILTER FABRIC	SQ YD	609
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	44

CODE NO	ITEM	UNIT	TOTAL QUANTITY
44000100	PAVEMENT REMOVAL	SQ YD	114
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1
50102400	CONCRETE REMOVAL	CU YD	4.0
50300225	CONCRETE STRUCTURES	CU YD	22.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	103.0
50300260	BRIDGE DECK GROOVING	SQ YD	554
50300300	PROTECTIVE COAT	SQ YD	554
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	2996
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	20890
50800515	BAR SPLICERS	EACH	314
50901050	STEEL RAILING, TYPE SM	FOOT	242
51500100	NAME PLATES	EACH	1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	71
59000200	EPOXY CRACK INJECTION	FOOT	25