

LOCATION	PREFORMED PAVEMENT MARKING	MODIFIED URETHANE PAVEMENT MARKING			GROOVING FOR RECESSED PAVEMENT MARKING	GROOVING FOR RECESSED PAVEMENT MARKING	AERIAL SPEED CHECK MARKING	SHORT TERM PAVEMENT MARKING	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKERS		WORK ZONE PAVEMENT MARKING REMOVAL	TEMPORARY PAVEMENT MARKING LINE 4"	PAVEMENT MARKING REMOVAL
	SKIP-DASH WHITE 4"	SOLID WHITE 4"	SOLID YELLOW 4"	SOLID WHITE 8"	5"	9"			ONE WAY CRYSTAL	ONE WAY AMBER	SQ FT	FOOT	SQ FT	
STATION TO STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	SQ FT	FOOT	SQ FT
FAI 57 NORTHBOUND														
635+25.00 TO 764+96.99	3240		12972		12972			3226	324	324		4479	25944	
765+00.00 TO 904+91.00	3500		13991		13991			3534	350	350		4843	27982	
638+28.00 TO 641+14.00				286		286			8	8				94
641+14.00 TO 657+84.00		1670			1670									556
657+84.00 TO 660+62.00				278		278			8	8				95
668+34.00 TO 748+00.00		7966			7966									2655
690+80.00 RT									12					
697+40.00 RT									12					
704+00.00 RT									12					
750+93.00 TO 754+66.00				373		373			10	10				122
754+66.00 TO 764+96.99		1031			1031									344
765+00.00 TO 776+35.00		1135			1135									378
776+35.00 TO 778+84.00				249		249			7	7				89
787+02.00 TO 904+91.00		11789			11789									3930
902+00.00 RT									12					
908+60.00 RT									12					
915+20.00 RT									12					
SUB-TOTAL	6740	23591	26963	1186	50554	1186	72	6760	707	707	0	9322	53926	8263
<b>OLYMPIAN RAMPS</b>														
RAMP A LT														
15+00.00 TO 15+40.00		40			40			8				14		
15+40.00 TO 15+90.00			50		50							17		
15+90.00 TO 18+65.00				275		275			7	7				
RAMP A RT														
11+02.00 TO 15+67.50								8						
15+00.00 TO 26+38.00		1138			1138			88				380		
RAMP B LT														
10+03.00 TO 12+89.00				286		286			7	7				
12+89.00 TO 13+39.00			50		50			4	3		1	17		
13+39.00 TO 13+79.00		40			40			4			1	14		
RAMP B RT														
9+10.00 TO 12+89.00									19	19		126		
9+10.00 TO 13+11.50		402			402			32				8		
13+11.50 TO 13+79.00		67			67			8				23		
<b>MARKET RAMPS</b>														
RAMP A LT														
3+05.00 TO 306+79.00				368		368			9	9				
306+72.59 TO 306+79.00				6		6								
306+79.00 TO 307+29.00			50		50			8	1		2	17		
307+29.00 TO 307+69.00		40			40				2			13		
RAMP A RT														
0+13.00 TO 6+72.59		660			660			56	33	33		220		
306+72.59 TO 307+69.00		96			96			8				32		
RAMP B LT														
331+48.00 TO 331+87.00		39			39			8				8		
331+87.00 TO 333+61.36				124		124			3	3		22		
0+00.00 TO 1+22.00				122		122			3	3				
RAMP B RT														
331+48.00 TO 333+61.36		213			213			16				72		
0+00.00 TO 9+40.00		940			940			72				313		
SUB-TOTAL	0	3675	150	1181	3825	1181	0	320	87	81	4	1296	0	0
TOTAL		27266	27113							788	4			
GRAND TOTAL	6740	54379	2367	54379	2367	72	7080	794	792	10618	53926	8263		

DELINEATORS

LOCATION	SINGLE WHITE	DOUBLE WHITE	SINGLE AMBER	DOUBLE AMBER	TRIPLE AMBER	REMOVAL
OLYMPIAN	EACH	EACH	EACH	EACH	EACH	EACH
RAMP A	15+60.00 RT		15+60.00 LT			2
	16+40.00 RT					1
	17+20.00 RT					1
		18+20.00 RT				1
		19+20.00 RT				1
		20+20.00 RT				1
		21+20.00 RT				1
		22+20.00 RT				1
		23+20.00 RT				1
		24+20.00 RT				1
		25+20.00 RT				1
		26+20.00 RT				1
		27+20.00 RT				1
RAMP B		634+90.00 RT (I-57)				1
		7+60.00 RT				1
		8+60.00 RT				1
		9+60.00 RT				1
		10+60.00 RT				1
		11+60.00 RT				1
	12+60.00 RT					1
	13+60.00 RT					1
MARKET ST						
RAMP A	307+32.00 RT		307+32.00 LT			2
		0+57.00 RT				1
		1+57.00 RT				1
		2+57.00 RT				1
		3+57.00 RT				1
		4+57.00 RT				1
		5+57.00 RT				1
		6+57.00 RT				1
RAMP B			331+50.00 LT			1
	332+00.00 RT					1
	332+75.00 RT					1
	333+50.00 RT					1
		0+00.00 RT				1
		1+00.00 RT				1
		2+00.00 RT				1
		3+00.00 RT				1
		4+00.00 RT				1
		5+00.00 RT				1
		6+00.00 RT				1
		7+00.00 RT				1
		8+00.00 RT				1
		9+00.00 RT				1
<b>CROSSOVERS</b>						
732+05.00 CL				2	2	2
805+43.00 CL				2	2	2
SUB-TOTAL	9	33	3	4	4	49
TOTAL			53			49

CHANGEABLE MESSAGE SIGN

LOCATION	DESCR.	* REQUIRED	CAL	X7015005
I-57 NB	PRIOR TO CONSTRUCTION	1	14	14
*I-57 NB (701400)	DURING STANDARD 701401 AND 701402	1	130	0
**I-57 NB (701400)	DURING STANDARD 701406	1	20	0
I-57 NB	PRIOR TO AND DURING U OF I GRADUATION DAY	1	5	5
I-74 WB	PRIOR TO AND DURING U OF I GRADUATION DAY	1	5	5
I-57 NB	PRIOR TO AND DURING U OF I MOVE IN DAY	1	5	5
I-74 WB	PRIOR TO AND DURING U OF I MOVE IN DAY	1	5	5
			TOTAL	34

\* INCLUDED IN COST OF STANDARD 701401 AND 701402

\*\* INCLUDED IN COST OF STANDARD 701406