STAGE ONE

GENERAL NOTES FOR STAGE CONSTRUCTION:

1. ALL SIGNS, TRAFFIC CONTROL EQUIPMENT, AND
TEMPORARY PAVEMENT MARKINGS SHALL BE IN
ACCORDANCE WITH THE LATEST VERSION OF
HIGHWAY STANDARD 701316 AND SHALL BE
INCLUDED IN THE CONTRACT UNIT PRICE EACH F

INCLUDED IN THE CONTRACT UNIT PRICE EACH FOR TRAFFIC CONTROL AND PROTECTION STANDARD 701316

- 2. ALL TEMPORARY BRIDGE TRAFFIC SIGNALS FOR CONSTRUCTION WILL BE MEASURED AS 1 (ONE)
- 3. PLACE RCA IN ADVANCE OF SIGNALS AS DIRECTED BY ENGINEER.
- 4. ENTRANCE TO E 3785 NORTH ROAD IS TO REMAIN OPEN AT ALL TIMES.
- 5. EXISTING STOP SIGN AT ENTRANCE TO E 3785 NORTH ROAD IS TO BE COVERED
- 6. AN RCA WITH SIGNALS AND A SIGNAL AHEAD SIGN ARE TO BE PLACED ON E 3785 AS DIRECTED BY THE ENGINEER.
- 7. ALL PRIVATE ENTRANCES ARE TO REMAIN OPEN AT ALL TIMES.
- 8. ALL TRAFFIC CONTROL ITEMS NOT SHOWN ON STAGE I & II PLAN VIEW SHALL BE PER REQUIREMENTS OF TRAFFIC CONTROL AND PROTECTION STANDARD 701316.



