

PIPE CULVERTS, CLASS A

TYP. SEC. #	LOCATION	TYPE 1			TYPE 2	
		15"	18"	24"	15"	18"
		(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)
	(AREA A)					
	[F. A. P. 63 (US 24 & IL 96)]					
(6)	STA. 301+80.00 RT		42.92			
	TOTAL AREA A		43			
	(AREA B)					
	[F. A. P. 63 (US 24 & IL 96)]					
(9)	STA. 314+50.00 RT			67.76		
	TOTAL AREA B			68		
	(AREA C)					
	[F. A. P. 506 (IL 96)]					
(12)	STA. 341+15.00 RT					49.20
(14)	STA. 348+80.00 TO STA. 348+98.30 LT	17.29				
(14)	STA. 352+00.00 RT				50.90	
	TOTAL AREA C	18			51	50
	PROJECT TOTAL	18	43	68	51	50

PRECAST REINFORCED CONCRETE END SECTIONS

TYP. SEC. #	LOCATION	15"	18"	24"	30"
		(EACH)	(EACH)	(EACH)	(EACH)
	(AREA A)				
	[F. A. P. 63 (US 24 & IL 96)]				
(5)	STA. 297+19.35, 29.89' LT.				1
(6)	STA. 301+80.00, 67.35' RT.		1		
	TOTAL AREA A		1		1
	(AREA B)				
	[F. A. P. 63 (US 24 & IL 96)]				
(9)	STA. 314+50.00, 0.91' RT.			1	
(9)	STA. 314+50.00, 80.81' RT.			1	
	TOTAL AREA B			2	
	(AREA C)				
	[F. A. P. 63 (US 24 & IL 96)]				
(12)	STA. 341+15.00, 72.27' RT.		1		
(14)	STA. 348+80.00, 4.41' LT.	1			
(14)	STA. 352+00.00, 51.02' RT.	1			
	TOTAL AREA C	2	1		
	PROJECT TOTAL	2	2	2	1

* FAP 63 (US 24); FAP 63 (US 24/IL 96); FAP 506 (IL 96)

FILE NAME :	USER NAME : sparksg	DESIGNED - JWC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\sparksg\08259630\067	BE31-ent-schedule.dgn	DRAWN - JWC	REVISED -		SCALE:	SHEET 17	OF 25	SHEETS	STA.	TO STA.	ADAMS	194	30
		CHECKED - RSC	REVISED -								CONTRACT NO. 72E31		
Default	PLOT DATE : Dec-14-2012 03:44:54PM	DATE -	REVISED -								ILLINOIS FED. AID PROJECT		