

GRATING FOR CONCRETE FLARED END SECTIONS

TYP. SEC. #	LOCATION	15"	18"	24"	30"
		(EACH)	(EACH)	(EACH)	(EACH)
(AREA A)					
[F. A. P. 63 (US 24 & IL 96)]					
(5)	STA. 297+19.35, 29.89' LT.				1
(6)	STA. 301+80.00, 67.35' RT.		1		
TOTAL AREA A			1		1
(AREA B)					
[F. A. P. 63 (US 24 & IL 96)]					
(9)	STA. 314+50.00, 0.91' RT.			1	
(9)	STA. 314+50.00, 80.81' LT.			1	
TOTAL AREA A				2	
(AREA C)					
[F. A. P. 63 (US 24 & IL 96)]					
(12)	STA. 341+15.00, 72.27' RT.		1		
(14)	STA. 348+80.00, 4.41' LT.	1			
(14)	STA. 352+00.00, 51.02' RT.	1			
TOTAL AREA C		2	1		
PROJECT TOTAL		2	2	2	1

STORM SEWERS CLASS A, TYPE 1

TYP. SEC. #	LOCATION	12"	15"	18"	24"	30"
		(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)
(AREA A)						
[F. A. P. 63 (US 24 & IL 96)]						
(5)	STA. 297+14.76, LT					6.5
(6)	STA. 301+80.00	5.3		23.0		
(6)	STA. 301+80.00 TO STA. 302+80.00 LT		97.5			
(6)	STA. 302+80.00, LT	5.3				
(6)	STA. 302+80.00 TO STA. 303+50.00	77.4				
(7)	STA. 304+80.00 TO STA. 305+50.00 LT	68.3				
(7)	STA. 305+50.00 TO STA. 306+90.00 LT		137.5			
(7)	STA. 306+90.00	23.2				
(7-8)	STA. 306+90.00 TO STA. 308+50.00 RT	158.2				
TOTAL AREA A		338	235.9	23	0	6.5
(AREA C)						
[F. A. P. 506 (IL 96)]						
(12)	STA. 339+48.00, RT	6.0				3.5
(12-13)	STA. 339+48.00 TO STA. 341+15.00		164.8			
(12)	STA. 341+15.00			14.0		
(14)	STA. 348+98.30				7.0	
TOTAL AREA C		6	164.8	14	7	3.5
PROJECT TOTAL		344	400	37	7	10

* FAP 63 (US 24); FAP 63 (US 24/IL 96); FAP 506 (IL 96)

FILE NAME :	USER NAME : sparksgw	DESIGNED - JWC	REVISED -
oi\pwwork\pwwork\sparksgw\d0299630\067	2E31-sht-schedule.dgn	DRAWN - JWC	REVISED -
Default	PLOT SCALE = 100.0000' / 1"	CHECKED - RSC	REVISED -
	PLOT DATE = Dec-14-2012 03:44:54PM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET 18 OF 25 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	(1)N.TS-2RS-5&(7)RS-3	ADAMS	194	31
CONTRACT NO.			72E31	
ILLINOIS FED. AID PROJECT				