

LOCATION	PATCHING SCHEDULE, CLASS A PATCHES (SQ YD)									SAW CUTS		TIE BARS		PATCHING REINFORCEMENT		
	LENGTH (FOOT)		FOOT	SQ YD	TY II	TY III	TY IV	TY II	TY III	TY IV	(FOOT)		(EACH)		(SQ YD)	
	PASSING	DRIVING	WIDTH	FULL DEPTH	PASSING			DRIVING			PASSING	DRIVING	PASSING	DRIVING	PASSING	DRIVING
ADAMS COUNTY																
13+02	12.00		12.00	16.0		16.0					72.0				16.0	
12+74	5.00		12.00	6.7	6.7						58.0				6.7	
12+44		8.00	12.00	10.7				10.7				64.0				10.7
11+13		8.00	12.00	10.7				10.7				64.0				10.7
11+01	15.00		12.00	20.0		20.0					78.0				20.0	
10+50		5.00	12.00	6.7				6.7				58.0				6.7
8+48	48.00		12.00	64.0			64.0				144.0		25		64.0	
7+40	5.00		12.00	6.7	6.7						58.0				6.7	
7+07	8.00		12.00	10.7	10.7						64.0				10.7	
6+83		25.00	12.00	33.3						33.3		98.0		13		33.3
6+83	25.00		12.00	33.3			33.3				98.0		13		33.3	
6+31	5.00		12.00	6.7	6.7						58.0				6.7	
6+15	10.00		12.00	13.3	13.3						68.0				13.3	
2+06		32.00	12.00	42.7						42.7		112.0		17		42.7
1+74		5.00	12.00	6.7				6.7				58.0				6.7
PIKE COUNTY																
1008+11	5.00		12.00	6.7	6.7						58.0				6.7	
1015+06	6.00		12.00	8.0	8.0						60.0				8.0	
1078+64		5.00	12.00	6.7				6.7				58.0				6.7
1140+25		5.00	12.00	6.7				6.7				58.0				6.7
1140+88		5.00	12.00	6.7				6.7				58.0				6.7
1155+78		5.00	12.00	6.7				6.7				58.0				6.7
1208+66		5.00	12.00	6.7				6.7				58.0				6.7
1225+49		5.00	12.00	6.7				6.7				58.0				6.7
1227+39		5.00	12.00	6.7				6.7				58.0				6.7
1230+83		5.00	12.00	6.7				6.7				58.0				6.7
1230+83	5.00		12.00	6.7	6.7						58.0				6.7	
1237+05	5.00		12.00	6.7	6.7						58.0				6.7	
1240+18		5.00	12.00	6.7				6.7				58.0				6.7
1240+36		5.00	12.00	6.7				6.7				58.0				6.7
1240+70		5.00	12.00	6.7				6.7				58.0				6.7
1242+30		5.00	12.00	6.7				6.7				58.0				6.7
1266+96		5.00	12.00	6.7				6.7				58.0				6.7
1335+62		22.00	12.00	29.3						29.3		92.0		12		29.3
1335+62	18.00		12.00	24.0		24.0					84.0				24.0	
1359+46		8.50	12.00	11.3				11.3				65.0				11.3
1389+32		18.00	12.00	24.0					24.0			84.0				24.0
1390+79		5.00	12.00	6.7				6.7				58.0				6.7
1391+98		5.00	12.00	6.7	6.7			6.7				58.0			6.7	6.7
23+10 **		5.00	16.00	8.9				8.9				58.0				8.9
ADAMS TOTAL																
				288.2	44.1	36.0	97.3	34.8	0.0	76.0	698.0	454.0	38.0	30.0	177.4	110.8
PIKE TOTAL																
				232.7	34.7	24.0	0.0	120.7	24.0	29.3	318.0	1169.0	0.0	12.0	58.7	174.0

** ENTRANCE OF RAMP

FILE NAME *	USER NAME * shhdn	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES EASTBOUND				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\shhdn\108312181\108312181.dgn	shh-schedule.dgn	DRAWN -	REVISED -						72	*	PIKE-ADAMS	7	4
PLOT SCALE * 48.0000 "/>													
DATE -	REVISED -	SCALE:	SHEET		OF	SHEETS	STA.	TO	STA.	ILLINOIS FED. AID PROJECT			