

GENERAL NOTES

- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY FROM CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. THE JULIE NUMBER IS 800-892-0123. A MINIMUM OF FORTY-EIGHT HOURS ADVANCE NOTICE IS REQUIRED. ANY DAMAGE TO THE UNDERGROUND FACILITIES, CAUSED BY THE CONTRACTOR SHALL BE REPAIRED TO THE SATISFACTION OF THE DEPARTMENT AT THE CONTRACTOR'S EXPENSE, INCLUDING TEMPORARY REPAIRS WHICH MAY BE REQUIRED TO KEEP THE FACILITY OPERATIONAL WHILE MATERIAL IS BEING OBTAINED TO MAKE PERMANENT REPAIRS. SPECIAL ATTENTION SHOULD BE GIVEN TO THE AREA ADJACENT TO THE APPROACH PAVEMENT WHERE FRENCH DRAINS ARE TO BE CONSTRUCTED.
- THE LOCATIONS OF THOSE BURIED AND ABOVEGROUND UTILITIES SHOWN ARE APPROXIMATE, ARE SHOWN FOR CONTRACTOR INFORMATIONAL USE ONLY, AND ARE NOT TO BE REFERENCED FOR CONSTRUCTIONS PURPOSES. THE IMPLIED PRESENCE OR ABSENCE OF UTILITIES IS NOT TO BE CONSTRUED BY THE OWNER, ENGINEER, CONTRACTOR, OR SUBCONTRACTORS TO BE AN ACCURATE AND COMPLETE REPRESENTATION OF UTILITIES THAT MAY OR MAY NOT EXIST ON THE CONSTRUCTION SITE. BURIED AND ABOVEGROUND UTILITY LOCATION, IDENTIFICATION, AND MARKING ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. REROUTING, DISCONNECTION, PROTECTION, ETC. OF ANY UTILITIES MUST BE COORDINATED BETWEEN THE CONTRACTOR, UTILITY COMPANY, AND OWNER. SITE SAFETY, INCLUDING THE AVOIDANCE OF HAZARDS ASSOCIATED WITH BURIED AND ABOVEGROUND UTILITIES, REMAINS THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
- THE THICKNESS OF HOT-MIX ASPHALT MIXTURES SHOWN ON THE PLANS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HOT-MIX ASPHALT MIXTURE IS PLACED.
- THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:
 

AGGREGATE MATERIALS	1.89	TONS/CU YD
BITUMINOUS MATERIAL (PRIME COAT)	0.00038	TON/SQ YD
AGGREGATE (PRIME COAT)	0.002	TON/SQ YD
HOT-MIX ASPHALT SURFACE COURSE	112	LBS/SQ YD/IN
HOT-MIX ASPHALT BINDER COURSE	112	LBS/SQ YD/IN
- ALL ELEVATIONS REFER TO U. S. G. S. MEAN SEA LEVEL DATUM.
- ANY REFERENCE TO A STANDARD IN THESE PLANS SHALL BE INTERPRETED TO MEAN THE EDITION AS INDICATED BY THE SUBNUMBER LISTED ON THE INDEX OF SHEETS OR THE COPY OF THE STANDARD INCLUDED IN THESE PLANS.
- UNLESS NOTED OTHERWISE, STATIONS AND OFFSETS REFER TO CENTERLINE OF PROJECT.
- IN ADDITION TO FIELD SURVEYS AND AERIAL SURVEYS, PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING FACILITIES HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD. SUCH VARIATIONS SHALL NOT BE A CAUSE FOR ADDITIONAL COMPENSATION DUE TO A CHANGE IN THE SCOPE OF THE WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.
- NO PASSING ZONES SHALL BE FIELD VERIFIED BY OPERATIONS 14 DAYS PRIOR TO PLACEMENT OF FINAL PAVEMENT MARKINGS.

COMMITMENTS:

THE FIELD/RESIDENT ENGINEER SHALL CONTACT STUDIES AND PLANS COVERING ANY MAJOR PLAN CHANGES TO MAKE SURE NO PREVIOUS COMMITMENTS (NOT LISTED) WERE MADE AFFECTING THE DESIGN, AND TO ALLOW IMPROVED DESIGN FOR THE FUTURE.

INDEX OF SHEETS

- 1 COVER SHEET
- 2 GENERAL NOTES, INDEX OF SHEETS
- 3-5 SUMMARY OF QUANTITIES
- 6-11 SCHEDULE OF QUANTITIES
- 12-24 TYPICAL SECTIONS
- 25-35 PLAN SHEETS
- 36 PAVEMENT MARKING PLAN SHEET
- 37-38 SUPER ELEVATION DETAIL SHEETS
- 39 BUTT JOINT DETAIL
- 40-41 ENTRANCE DETAIL
- 42-44 ENTRANCE SCHEDULE
- 45-47 SIGN SCHEDULE

The following mixture requirements are applicable for this project:

Mixture Number	1	2	3	4	4
Mixture Use(s)	HMA SURFACE & HMA SHOULDERS	LEVELING BINDER	INCIDENTAL SURFACING	PAVEMENT PATCHING	6.5" HMA SHOULDERS
AC/PG:	PG 64-22	PG64-22	PG64-22	PG64-22	PG64-22
Design Air Voids:	4.0% @ N70	4.0% @ N70	4.0% @ N50	4.0% @ N70	4.0% @ N50
Mixture Composition: (Gradation Mixture)	IL 9.5 OR 12.5	IL 9.5	IL 9.5 OR 12.5	IL 19.0	IL 19.0
Friction Aggregate:	MIX "C"	N/A	MIX "C"	N/A	N/A

<b>DISTRICT SIX</b>	
EXAMINED <u>10/15</u> 20 <u>12</u>	
<i>Bill Boyer</i>	
OPERATIONS ENGINEER	
EXAMINED <u>OCT 20</u> 20 <u>12</u>	
<i>Jim [Signature]</i>	
PROJECT IMPLEMENTATION ENGINEER	
EXAMINED <u>Oct. 15</u> 20 <u>12</u>	
<i>2RMLJ</i>	
PROGRAM DEVELOPMENT ENGINEER	