

HMA SURFACE REMOVAL - BUTT JOINT

LOCATION	LENGTH (FOOT)	AREA (SQ YD)
IL 125		
STA 445+40.00	30	80.0
STA 1075+30.00	30	80.0
TOTAL		160.0

NOTE:
SEE ENTRANCE SCHEDULE FOR ADDITIONAL
HMA SURFACE REMOVAL - BT. JT. QUANTITY

AGGREGATE SHOULDERS, TYPE B

LOCATION	LT / MED SHOULDER WIDTH (FT)	RT/ OS SHOULDER WIDTH (FT)	AVERAGE THICKNESS (IN)	AREA (SQ YD)	WEIGHT (TONS)
IL 125					
STA 455+40.00 TO STA 472+69.16	5	5	6	1,921.29	605.21
STA 472+69.16 BK = STA 472+67.76 AH					
STA 472+67.76 TO STA 522+67.03	5	5	6	5,554.74	1,749.74
STA 522+67.03 BK = STA 522+71.69 AH					
STA 522+71.69 TO STA 549+81.64	5	5	6	3,011.06	948.48
STA 549+81.64 BK = STA 549+69.10 AH					
STA 549+69.10 TO STA 629+37.01	5	5	6	8,853.23	2,788.77
STA 629+37.01 BK = STA 629+30.80 AH					
STA 629+30.80 TO STA 729+13.82	5	5	6	11,092.24	3,494.06
STA 729+13.82 BK = STA 729+13.40 AH					
STA 729+13.40 TO STA 754+84.89	5	5	6	2,857.21	900.02
STA 754+84.89 BK = STA 754+84.34 AH					
STA 754+84.34 TO STA 767+85.66	5	5	6	1,445.91	455.46
STA 767+85.66 BK = STA 767+85.99 AH					
STA 767+85.99 TO STA 909+98.22	5	5	6	15,791.37	4,974.28
STA 909+98.22 BK = STA 909+97.41 AH					
STA 909+97.41 TO STA 918+19.03	5	5	6	912.01	287.28
STA 918+19.03 BK = STA 918+18.96 AH					
STA 918+18.96 TO STA 1015+00.00	5	5	6	10,756.71	3,388.36
STA 1015+00.00 TO STA 1033+91.74	3	3	2	1,261.16	132.42
STA 1033+91.74 BK = STA 1033+91.48 AH					
STA 1033+91.48 TO STA 1075+30.00	3	3	2	2,759.01	289.70
TOTAL					20,013.8

TEMPORARY RAMP

LOCATION	LENGTH (FOOT)	AREA (SQ YD)
IL 125		
STA 445+40.00	5	13.33
STA 1075+00.00	5	13.33
SIDE ROADS		
DUNCAN AVE.	5	27.50
COUNTY SHED RD.	5	42.22
BEARDSTOWN RD.	5	54.44
BURLINGAME RD.	5	25.83
SUGAR GROVE RD.	5	23.33
WALNUT RD.	5	25.56
CAREY LN.	5	29.44
ELEVATOR RD.	5	21.11
PHILADELPHIA RD.	5	20.56
WATKINS RD.	5	15.56
DEVLIN LN.	5	17.78
KERSHAW LN.	5	18.33
LOCUST LN.	5	15.56
FRANKLIN LN.	5	52.22
PHILADELPHIA RD.	5	37.22
HALL RD.	5	23.89
PANTHER GROVE RD.	5	28.89
CENTINARY RD.	5	19.44
CANNON RD.	5	26.11
KEENEY RD.	5	18.33
NEWMANSVILLE RD.	5	40.00
FREMONT ST.	5	50.00
THREE MILE RD.	5	13.33
TOTAL		673.3