



STA 121+00 TO STA 128+00

NOTE:
SEE HIGHWAY STD. 6420006, SCHEDULES OF QUANTITIES,
AND SHEET 23 FOR PLACEMENT OF PROPOSED CENTERLINE
RUMBLE STRIPS.

EXISTING LEGEND

- ① EX PCC PAVEMENT (8'')
- ② EX BIT. BASE COURSE WIDENING (8'' & VAR.)
- ③ EX BIT. OVERLAY (3'')
- ④ EX BIT. OVERLAY (2-1/2'')
- ⑤ EX BRICK SURFACING
- ⑥ EX 8'' SHOULDER (BAM)
- ⑦ EX PCC BASE COURSE WIDENING (8'')
- ⑧ EX HOT-MIX ASPHALT SHOULDER 8''
- ⑨ EX BIT BASE COURSE (8'' & VAR.)
- ⑩ EX SUB-BASE GRANULAR MATERIAL
- ⑪ EX GRANULAR EMBANKMENT SPECIAL-THICKNESS VAR.
- ⑫ EX RALUMAC MICRO-SURFACING
- ⑬ EX AGG SHOULDER, TYPE B
- ⑭ EX CONCRETE PAVEMENT
- ⑮ EX CONCRETE WIDENING
- ⑯ EX HMA OVERLAY, 2''
- ⑰ EX HMA WIDENING, 9''
- ⑱ EX CONCRETE GUTTER, TY B (SPECIAL)
- ⑲ EX HMA OVERLAY, 5 1/2 & VARIABLE

PROPOSED LEGEND

- (A) PROP LEVELING BINDER (MACHINE METHOD),
N70 (3/4'')
- (B) PROP HOT-MIX ASPHALT SURFACE COURSE,
MIX "D", N70 (1-1/2'')
- (C) PROP HMA SURFACE REMOVAL VAR. DEPTH, 3/4'' TYP
- (D) PROP MODIFIED URETHANE PAV'T MARKING - LINE 5''
- (E) PROP AGG SHOULDER, TYPE B
- (F) PROP HOT - MIX ASPHALT SHOULDER (AVG. DEPTH = 1 1/2'')

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TYPICAL SECTIONS		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	Default	DRAWN -	REVISED -				662	*	SANGAMON	28	7
		CHECKED -	REVISED -		SCALE: SHEET 1 OF 5 SHEETS STA. TO STA.		CONTRACT NO. 72F72				
		DATE -	REVISED -		ILLINOIS FED. AID PROJECT						