

INDEX OF SHEETS:

1. COVER SHEET
2. INDEX OF SHEETS, STANDARDS, GENERAL NOTES & SIGNATURES.
- 3-4. PROJECT LOCATION, STATION EQUATIONS, OMISSION STATIONS
5. SUMMARY OF QUANTITIES
- 6-11. DRAINAGE PLANS
- 12-28. EXISTING & PROPOSED DRAINAGE STRUCTURE DETAILS

STANDARDS

STANDARD NO.	DESCRIPTION
420001-07	PAVEMENT JOINTS
606211-03	OUTLETS TYPE 2 FOR TYPE B GUTTER
701001-02	OFF-ROAD OPERATIONS, 2L, 2W, 4.5 M (15') MINIMUM FROM EDGE OF PAVEMENT - > 45 MPH
701006-04	OFF-ROAD OPERATIONS, 2L, 2W, 4.5 M (15') TO 600 MM (24") FROM PAVEMENT EDGE
701201-04	LANE CLOSURE, 2L, 2W, DAY ONLY FOR SPEEDS ≥ 45 MPH
701326-04	LANE CLOSURE, 2L, 2W, PAVEMENT WIDENING FOR SPEEDS ≥ 45 MPH
701901-02	TRAFFIC CONTROL DEVICES

INLET LOCATED AT FOLLOWING STATIONS:

697+89 LT	943+75 LT
706+50 LT	947+95 LT
711+75 LT	957+62 LT
716+25 LT	963+50 LT
719+35 LT	968+88 LT
763+50 LT	978+50 LT
787+95 LT	983+25 LT
793+10 LT	994+50 LT
811+80 LT	1001+88 LT
825+00 LT	1005+50 LT
881+50 LT	1038+10 LT
909+00 LT	1041+31 LT
915+90 LT	1046+30 LT
921+75 LT	1048+35 LT
923+75 LT	1049+75 LT
925+50 LT	1094+50 LT
939+75 LT	

GENERAL NOTES

- GUTTER SHALL BE REMOVED AT BEGINING OF SECTION B-B AND AT THE CONSTRUCTION JOINT (C.J.) AT ALL 33 LOCATIONS. (SEE SHEET NO. 12)
- CONSTRUCT ONLY TOP 8" OF THE INLET AND REMAINDER OF THE GUTTER STARTING AT SECTION B-B AT ALL 33 LOCATIONS. (SEE SHEET NO. 13)
- FURNISHED EXCAVATION IS INCIDENTAL TO EACH LOCATION. AN ESTIMATE OF 1 CU. YD. OF FURNISHED EXCAVATION IS ESTIMATED FOR EACH LOCATION.
- FURNISHED EXCAVATION SHALL INCLUDE SEEDING AND MULCH.
- ANCHOR BOLTS: THE LENGHT OF THE ANCHOR BOLTS IS 6". 3" SHALL BE EMBADDED IN THE EXISTING CONCRETE AND 3" SHALL BE EMBADDED IN THE PROPOSED CONCRETE.

MIXTURE REQUIREMENTS

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT		
MIXTURE USE(S):	TOP LIFT SHOULDER	BOTTOM LIFT SHOULDER
AC/PG:	PG 64-22	PG 64-22
DESIGN AIR VOIDS:	4.0% @ N50	4.0% @ N50
MIXTURE COMPOSITION:	IL-9.5	IL-19.0
FRICTION AGGREGATE:	MIX "C"	N/A

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS
DISTRICT 6

EXAMINED 2/9 20 13

Bill Hagan
ENGINEER OF OPERATIONS

EXAMINED JAN 15 20 13

Tommy Furt
ENGINEER OF PROJECT IMPLEMENTATION

EXAMINED January 16 20 13

ARNOLD
ENGINEER OF PROGRAM DEVELOPMENT