

SUMMARY OF QUANTITIES				CONSTRUCTION CODE			
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL 20% STATE	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY	
				ROADWAY 0005	TRAFFIC SIGNALS 0021	SIDEWALK 0021	
35101800	AGGREGATE BASE COURSE, TYPE B 6"	△ SQ YD	126	126			
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	121	121			
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	△ SQ YD	2,017	2,017			
35800100	PREPARATION OF BASE	SQ YD	1,111	1,111			
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	108	108			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.3	3.3			
40600300	AGGREGATE (PRIME COAT)	TON	16	16			
40600635	LEVELING BINDER (MACHINE METHOD), N70	△ TON	516	516			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	832	832			
40600990	TEMPORARY RAMP	SQ YD	104	104			
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	154	154			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	△ TON	896	896			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	387	387			
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	242	242			

△ REVISED 4-16-2013

**CEC**  
Cummins  
Engineering  
Corporation  
Civil and Structural Engineering

JOB - 2265.11  
FILE NAME - 0672F74-sh1-500.dgn  
PLOT SCALE - 20.0000' / IN.  
PLOT DATE - 2/4/2013

DESIGNED - NAK  
DRAWN - SJS  
CHECKED - NAK  
DATE - 10/8/2012

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

S.B.I. RTE. 126	SECTION 0101 1-2	COUNTY SANGAMON	TOTAL SHEETS 93	SHEET NO. 5
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT CONTRACT NO. 72F74		