


126

SUMMARY OF QUANTITIES				CONSTRUCTION CODE					
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL 20% STATE	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY			
				ROADWAY	TRAFFIC SIGNALS	SIDEWALK			
				0005	0021	0021			
20200100	EARTH EXCAVATION	CU YD	2,300	2,295		5			
20800150	TRENCH BACKFILL	CU YD	36	36					
* 25000200	SEEDING, CLASS 2	ACRE	1.1	1.0		0.1			
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	95	89		6			
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	95	89		6			
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	95	89		6			
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.1	2.0		0.1			
* 25100125	MULCH, METHOD 3	ACRE	1.1	1.0		0.1			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	105	100		5			
28000305	TEMPORARY DITCH CHECKS	FOOT	24	24					
28000400	PERIMETER EROSION BARRIER	FOOT	90	90					
28000500	INLET AND PIPE PROTECTION	EACH	18	17		1			
31100700	SUBBASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	2,489	2,489					
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	929	929					

*SPECIALTY ITEM

 Cummins Engineering Corporation <small>Civil and Structural Engineering</small>	JOB # 2265.11 FILE NAME : D672F74.sht-500.dgn PLOT SCALE : 20.0000 "/>	DESIGNED - NAK DRAWN - SJS CHECKED - NAK DATE - 10/8/2012	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				S.B.I. RTE. 126	SECTION 1101 1-2	COUNTY SANGAMON	TOTAL SHEETS 93	SHEET NO. 4
	PLOT DATE : 2/4/2013	DATE - 10/8/2012	SCALE:		SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 72F74				