

SUMMARY OF QUANTITIES				CONSTRUCTION CODE					
CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	80% FEDERAL 20% STATE	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY			
				ROADWAY	TRAFFIC SIGNALS	SIDEWALK			
				0005	0021	0021			
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	75	75					
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	121	121					
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SQ YD	2,003	2,003					
35800100	PREPARATION OF BASE	SQ YD	798	798					
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	98	98					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.3	3.3					
40600300	AGGREGATE (PRIME COAT)	TON	16	16					
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	513	513					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	832	832					
40600990	TEMPORARY RAMP	SQ YD	104	104					
40603085	HOT-MIX ASPHALT BINDER COURSE, 1L-19.0, N70	TON	154	154					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	895	895					
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	348	348					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	242	242					



JOB # 2265.11  
 FILE NAME : 0672F74\*sh1-500.dgn  
 PLOT SCALE : 20.0000 / 1/4"  
 PLOT DATE : 2/4/2013

DESIGNED - NAK  
 DRAWN - SJS  
 CHECKED - NAK  
 DATE - 10/8/2012

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

S.B.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
126	(110) 1-2	SANGAMON	93	5
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 72F74	