

| SUMMARY OF QUANTITIES | | | | CONSTRUCTION CODE | | | | | |
|-----------------------|--|-------|-------------------------|--------------------------|-------------------------------------|-------------------------|--|--|--|
| CODE NO. | ITEM | UNIT | URBAN TOTAL QUANTITY | 80% FEDERAL 20% STATE | 80% FEDERAL 15% STATE 5% CITY | 80% FEDERAL 20% CITY | | | |
| | | | | ROADWAY | TRAFFIC SIGNALS | SIDEWALK | | | |
| | | | | 0005 | 0021 | 0021 | | | |
| 42400100 | PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH | SQ FT | 1,630 | | | 1,630 | | | |
| 42400410 | PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH | SQ FT | 69 | | | 69 | | | |
| 42400800 | DETECTABLE WARNINGS | SQ FT | 113 | | | 113 | | | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 2,335 | 2,335 | | | | | |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 285 | 285 | | | | | |
| 44000300 | CURB REMOVAL | FOOT | 6 | 6 | | | | | |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 247 | 247 | | | | | |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 96 | | | 96 | | | |
| 44004250 | PAVED SHOULDER REMOVAL | SQ YD | 167 | 167 | | | | | |
| 44200108 | PAVEMENT PATCHING, TYPE II, 9 INCH | SQ YD | 149 | 149 | | | | | |
| 44213204 | TIE BARS 3/4" | EACH | 112 | 112 | | | | | |
| 44300200 | STRIP REFLECTIVE CRACK CONTROL TREATMENT | FOOT | 1,037 | 1,037 | | | | | |
| 48102100 | AGGREGATE WEDGE SHOULDER, TYPE B | TON | 142 | 142 | | | | | |
| 48203023 | HOT-MIX ASPHALT SHOULDERS, 6 1/2" | SQ YD | 2,458 | 2,458 | | | | | |



JOB # 2265.11
 FILE NAME : 0872F74-shr-500.dgn
 PLOT SCALE : 28.0000 / IN.
 PLOT DATE : 2/4/2013

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 10/8/2012

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

| | | | | |
|-----------------------|----------------------|---------------------------|--------------------|----------------|
| S.B.I. RTE. 126 | SECTION (110) 1-2 | COUNTY SANGAMON | TOTAL SHEETS 93 | SHEET NO. 6 |
| FED. ROAD DIST. NO. | | ILLINOIS FED. AID PROJECT | | |
| CONTRACT NO. 72F74 | | | | |