

SUMMARY OF QUANTITIES				CONSTRUCTION CODE							
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN							
				80% FEDERAL 20% STATE	80% FEDERAL 15% STATE 5% CITY	80% FEDERAL 20% CITY					
				ROADWAY 0005	TRAFFIC SIGNALS 0021	SIDEWALK 0021					
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	336		336						
* 87500600	TRAFFIC SIGNAL POST, 10 FT.	EACH	1		1						
* 87501200	TRAFFIC SIGNAL POST, 16 FT.	EACH	2		2						
* 87800115	CONCRETE FOUNDATION, TYPE A	EACH	4		4						
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	13		13						
* 87900200	DRILL EXISTING HANDHOLE	EACH	7		7						
* 88030230	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION, BRACKET MOUNTED	EACH	1		1						
* 88030240	SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	1		1						
* 88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2		2						
* 88102747	PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	1		1						
* 88102757	PEDESTRIAN SIGNAL HEAD, LED, 3-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2		2						
* 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	4		4						
* 88600100	DETECTOR LOOP, TYPE I	FOOT	800		800						
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	12		12						

*SPECIALTY ITEM



JOB : 2265.11
 FILE NAME : 0672F74-aht-500.dgn
 PLOT SCALE : 20.0000 / IN.
 PLOT DATE : 2/4/2013

DESIGNED - NAK
 DRAWN - SJS
 CHECKED - NAK
 DATE - 10/8/2012

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

S.B.I. RTE. 126	SECTION (110) 1-2	COUNTY SANGAMON	TOTAL SHEETS 93	SHEET NO. 11
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
CONTRACT NO. 72F74				