

STP FUNDING IS WEST OF I-172 AND NHS FUNDING IS EAST OF I-172

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	L2AE		L050		CONSTRUCTION CODE			
				STP FUNDS		NHS FUNDS					
				80% FED	20% STATE	80% FED	20% STATE				
				ROADWAY	0005	ROADWAY	0005				
				RURAL	RURAL						
* 78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	380	176		204					
* 78009012	MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	FOOT	227	102		125					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	146	73		73					
* 78200300	PRISMATIC CURB REFLECTOR	EACH	171	85		86					
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	12	6		6					
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	1		1					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	146	73		73				
	Z0041500	PLUG EXISTING CULVERTS	EACH	2	1		1				
	X6431120	REMOVE IMPACT ATTENUATOR SAND MODULE	EACH	2	1		1				
+	X0320157	CLEANING UNDERDRAIN OUTLETS	EACH	2	1		1				
	X0322279	OUTLET MARKER	EACH	4	1		3				
+	X0325893	CLEAN EXISTING END SECTION	EACH	2	2						
	X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SO FT	12236	6068		6168				
	X4403300	CONCRETE MEDIAN REMOVAL	SO FT	650	333		317				

* SPECIALTY ITEM + NON-PARTICIPATING 100% STATE

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
q:\201\111808224\1-2 - us 24 over tractor creek - roadway plan\us 24 5 1-172\cod		DRAWN 06/27/95-ahf-Summary.dgn	REVISED			63	(IRS-6)	ADAMS	24	7
PLOT SCALE - 1/8"=1'-0"	CHECKED	REVISED				SCALE: none	SHEET NO. 5 OF 6 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT
PLOT DATE - 10/18/2012	DATE	REVISED				CONTRACT NO. 72F76				