

EARTH EXCAVATION / GRANULAR SUBBASE SCHEDULE

ITEM	UNIT	TOTAL
EARTH EXCAVATION	CU YD	700
SUBBASE GRANULAR MATERIAL, TYPE B	TON	1430

ITEMS IN THIS SCHEDULE ARE ESTIMATED QUANTITIES TO BE USED FOR GROUND IMPROVEMENTS FOR PLACEMENT OF SUBBASE GRANULAR MATERIAL UNDER BASE COURSE, MEDIANS, CURB AND GUTTER, ETC., AS DIRECTED BY THE ENGINEER. IT MAY BE REDUCED, INCREASED, OR DELETED BY THE ENGINEER BASED ON ACTUAL FIELD CONDITIONS. NO WORK INVOLVING THESE ESTIMATED QUANTITIES SHALL BE PERFORMED WITHOUT THE DIRECTION AND APPROVAL OF THE ENGINEER.

EARTH EXCAVATION

20200500

STATION TO STATION	SIDE	CU YD
FAP 63 (US 24) - NHS FUNDING		
2154+49.7 2155+07.0	LT	3.5
2154+49.7 2155+20.0	RT	4.3
RAMP B - NHS FUNDING		
0+23.1 1+79.3	RT	28.5
0+23.1 1+79.3	LT	47.1
RAMP C - STP FUNDING		
22+12.6 23+41.2	RT	17.3
22+12.6 23+41.2	LT	19.0
TOTAL		119.8
USE		120

NOTE: THIS QUANTITY USED FOR EXCAVATION FOR BASE COURSE, BASE COURSE WIDENING, ETC., WHEN AT THE EDGE OF PAVEMENT.

GRADING AND SHAPING DITCHES

21400100

STATION TO STATION	SIDE	FOOT
FAP 63 (US 24) - NHS FUNDING		
2156+59.0 2157+59.0	LT	100
RAMP A - NHS FUNDING		
18+80.0 20+33.0	RT	153
TOTAL		253

INLET AND PIPE PROTECTION

28000500

STATION	SIDE	EACH
FAP 63 (US 24) - NHS FUNDING		
2157+59.0	LT	1
2164+00.0	RT	1
TOTAL		2

RIPRAP SCHEDULE

28100707 28200200

STATION TO STATION	SIDE	WIDTH	STONE DUMPED CLASS A4	FILTER FABRIC
			SO YD	
FAP 63 (US 24) - NHS FUNDING				
2156+59.0 2157+59.0	LT	10.0	111.1	111.1
RAMP A - NHS FUNDING				
18+80.0 20+33.0	RT	13.0	260.0	260.0
TOTALS			371.1	371.1
USE			372	372

PCC BASE COURSE SCHEDULE

35300605 35300720 31101000

STATION TO STATION	SIDE	PCC BASE COURSE 11 1/4"	PCC BASE COURSE 13"	SUBBASE GRANULAR MATERIAL TY B
		SO YD	SO YD	TON
FAP 63 (US 24) - NHS FUNDING				
2154+49.7 2155+07.0	LT		15.1	3.4
2154+49.7 2155+20.0	RT		18.8	4.3
2164+61.6 2165+17.1	LT & RT	11.5		
2165+78.5 2166+56.8	RT	23.5		
FAP 63 (US 24) - STP FUNDING				
2176+82.8 2177+59.8	LT	22.7		
2178+16.1 2178+68.6	LT & RT	5.5		
RAMP A - NHS FUNDING				
20+20.8 20+43.7	LT & RT	10.0		
RAMP B - NHS FUNDING				
0+23.1 1+79.3	RT		184.3	42.0
0+23.1 1+79.3	LT		179.7	40.9
RAMP C - STP FUNDING				
22+12.6 23+41.2	RT		155.9	35.5
22+12.6 23+41.2	LT		99.2	22.6
23+13.7 23+33.7	LT & RT	14.8		
TOTALS		87.9	653.0	148.7
USE		88	653	149

MISCELLANEOUS PAVING ITEMS SCHEDULE

ITEM	UNIT	TOTAL
CONSTRUCTING TEST STRIP	EACH	2
TEMPORARY RAMP	SO YD	500
BITUMINOUS MATERIALS (PRIME COAT)	TON	13.5
AGGREGATE (PRIME COAT)	TON	71

THE SCHEDULE FOR MISCELLANEOUS PAVING ITEMS ARE ESTIMATED QUANTITIES. IT MAY BE REDUCED, INCREASED, OR DELETED BY THE ENGINEER BASED ON ACTUAL FIELD CONDITIONS. NO WORK INVOLVING THESE ESTIMATED QUANTITIES SHALL BE PERFORMED WITHOUT THE DIRECTION AND APPROVAL OF THE ENGINEER.

AGGREGATE WEDGE SHOULDERS, TYPE B

48102100

STATION TO STATION	SIDE	TON
FAP 63 (US 24) - NHS FUNDING		
2154+49.7 2170+59.1	LT	64.4
2154+49.7 2170+91.5	RT	71.3
FAP 63 (US 24) - STP FUNDING		
2172+46.3 2188+11.9	LT	67.4
2172+78.6 2188+15.4	RT	65.0
RAMP A - NHS FUNDING		
19+61.1 20+51.3	LT	3.6
19+61.1 20+51.3	RT	5.3
RAMP B - NHS FUNDING		
0+23.1 1+79.3	LT	9.5
0+23.1 1+79.3	RT	10.4
RAMP C - STP FUNDING		
22+12.6 23+41.8	LT	5.5
22+12.6 23+41.8	RT	9.5
RAMP D - STP FUNDING		
0+23.8 1+16.7	LT	3.6
0+23.8 1+16.7	RT	7.0
TOTAL		322.5
USE		323

ROADWAY PAVING SCHEDULE

44000165 40603085 40603315

LOCATION STATION TO STATION	SIDE	HMA SURF REM 4"	BINDER COURSE IL-19.0, N70	HMA SURFACE COURSE MIX "C", N70
		SO YD		TON
FAP 63 (US 24) - NHS FUNDING				
2154+49.7 2171+69.0	LT & RT	5967.0	753.5	502.2
FAP 63 (US 24) - STP FUNDING				
2171+69.0 2188+43.3	LT & RT	5863.2	739.6	493.0
RAMP A - NHS FUNDING				
19+61.1 20+51.3	LT & RT	516.3	65.4	43.4
RAMP B - NHS FUNDING				
0+23.1 1+79.3	LT & RT	563.3	71.1	47.3
RAMP C - STP FUNDING				
22+12.6 23+41.8	LT & RT	558.3	71.5	47.6
RAMP D - STP FUNDING				
0+23.8 1+16.7	LT & RT	442.8	56.0	37.2
TOTALS		13910.9	1757.1	1170.7
USE		13911	1758	1171

SHOULDER PAVING SCHEDULE

44000156 48203100

LOCATION STATION TO STATION	SIDE	HMA SURF REM 1 3/4"	HMA SHLDS
		SO YD	TON
FAP 63 (US 24) - NHS FUNDING			
2154+49.7 2171+69.0	LT	1613.8	135.6
2154+49.7 2171+69.0	RT	1597.7	134.2
FAP 63 (US 24) - STP FUNDING			
2171+69.0 2188+43.3	LT	1682.8	141.4
2171+69.0 2188+43.3	RT	1661.8	139.6
RAMP A - NHS FUNDING			
19+61.1 20+51.3	LT	39.2	3.3
19+61.1 20+51.3	RT	108.1	9.1
RAMP B - NHS FUNDING			
0+23.1 1+79.3	LT	87.3	7.4
0+23.1 1+79.3	RT	184.3	15.5
RAMP C - STP FUNDING			
22+12.6 23+41.8	LT	57.4	4.9
22+12.6 23+41.8	RT	155.9	13.1
RAMP D - STP FUNDING			
0+23.8 1+16.7	LT	59.0	5.0
0+23.8 1+16.7	RT	140.1	11.8
TOTALS		7387.1	620.9
USE		7388	621

ENTRANCE SCHEDULE

40800050 44000156

STATION	SIDE	TYPE	WIDTH	AREA (SQ YD)	INCIDENTAL HMA SURFACING	HMA SURF REM 1 3/4"
					TON	SO YD
FAP 63 (US 24) - NHS FUNDING						
2158+00.0	LT	AC RD	VAR	65.5	5.5	65.5
TOTAL					5.5	65.5
USE					6	66

PAVEMENT PATCHING SCHEDULE

44200152 44200156 44200160 44200162

STATION	TYPE I 13 INCH	TYPE II 13 INCH	TYPE III 13 INCH	TYPE IV 13 INCH
	SO YD			
IDOT PATCHING SURVEY	45	825	430	125
TOTALS	45	825	430	125

NOTE: SPLIT EQUALLY PER FUNDING SOURCE IN SUMMARY OF QUANTITIES. THE ENGINEER WILL ADJUST BASED ON ACTUAL FIELD CONDITIONS.