

COMBINATION CONCRETE CURB AND GUTTER SCHEDULE

STATION TO STATION	SIDE	60608552 60608600 42001300		PROTECTIVE COAT	
		CONCRETE C & G M-4.06	CONCRETE C & G M-6.06		
		FOOT	SO YD		
FAP 63 (US 24) - NHS FUNDING					
2159+83.9	2165+04.1	LT	522.2		82.2
2159+83.9	2165+04.1	RT	520.3		81.9
2168+16.9	2171+69.0	LT	352.6		55.5
2168+16.9	2171+69.0	RT	352.1		55.5
FAP 63 (US 24) - STP FUNDING					
2171+69.0	2175+21.1	LT	352.1		55.5
2171+69.0	2175+21.1	RT	354.2		55.8
2178+26.0	2183+24.7	LT	499.0		78.5
2178+26.0	2183+24.7	RT	500.4		78.8
RAMP A - NHS FUNDING					
20+20.8	20+43.7	LT & RT		71.8	13.3
RAMP C - STP FUNDING					
23+13.7	23+33.7	LT & RT		54.8	10.2
TOTALS			3452.9	126.6	567.2
USE			3453	127	568

CONCRETE MEDIAN SURFACE SCHEDULE

STATION TO STATION	SIDE	60618300 42001300	
		CONCRETE MED SURF 4 INCH	PROTECTIVE COAT
		SO FT	SO YD
FAP 63 (US 24) - NHS FUNDING			
2159+83.9	2161+69.9	LT & RT	1422.7
2161+69.9	2165+04.1	LT & RT	4896.7
2168+16.9	2171+69.0	LT & RT	3844.3
FAP 63 (US 24) - STP FUNDING			
2171+69.0	2175+21.1	LT & RT	3844.3
2178+26.0	2181+49.4	LT & RT	4700.0
2181+49.4	2183+24.7	LT & RT	1307.7
RAMP A - NHS FUNDING			
20+20.8	20+43.7	LT & RT	236.9
RAMP C - STP FUNDING			
23+13.7	23+33.7	LT & RT	137.1
TOTALS			20389.7
USE			20390

CORRUGATED MEDIAN SCHEDULE

STATION TO STATION	SIDE	60624600 42001300	
		CORRUGATED MEDIAN	PROTECTIVE COAT
		SO FT	SO YD
FAP 63 (US 24) - NHS FUNDING			
2158+47.7	2160+53.6	RT	799.3
FAP 63 (US 24) - STP FUNDING			
2182+58.4	2184+60.8	RT	787.8
TOTALS			1587.1
USE			1588

CONCRETE MEDIAN SCHEDULE

STATION TO STATION	SIDE	X6065701 42001300	
		CONCRETE MEDIAN SM-4.06	PROTECTIVE COAT
		SO FT	SO YD
FAP 63 (US 24) - NHS FUNDING			
2159+76.7	2159+83.9	RT	27.8
2165+04.1	2165+11.3	RT	47.6
2166+04.8	2168+16.9	RT	1218.7
FAP 63 (US 24) - STP FUNDING			
2175+21.1	2177+34.8	LT	1228.5
2178+18.9	2178+26.0	LT & RT	47.7
2183+24.7	2183+31.8	RT	27.9
TOTALS			2598.2
USE			2599

SIGN SCHEDULE

STATION	SIDE	TYPE	72000100 72800100		
			SIGN PANEL TY 1	TELESCOPING STEEL SIGN SUPPORT	
		SO FT	FOOT		
RAMP A - NHS FUNDING					
20+18	LT	RI-1 (STOP SIGN)	9		15
RAMP C - STP FUNDING					
23+12	LT	RI-1 (STOP SIGN)	9		15
TOTALS			18		30

CLEANING UNDERDRAIN OUTLETS

X0320157			
STATION	SIDE	OFFSET	EACH
FAP 63 (US 24) - STP FUNDING			
2177+59.6	LT	45.0	1
RAMP B - NHS FUNDING			
1+32.2	RT	19.0	1
TOTAL			2

OUTLET MARKER

X0322279			
STATION	SIDE	EACH	
FAP 63 (US 24) - NHS FUNDING			
2162+99.4	LT	1	
FAP 63 (US 24) - STP FUNDING			
2177+59.6	LT	1	
RAMP B - NHS FUNDING			
1+32.2	RT	1	
1+50.0	LT	1	
TOTAL			4

CLEAN EXISTING END SECTION

X0325893			
STATION	SIDE	OFFSET	EACH
FAP 63 (US 24) - STP FUNDING			
2173+66.0	RT	51.2	1
2173+93.4	LT	52.9	1
TOTAL			2

GUARDRAIL SCHEDULE

STATION TO STATION	SIDE	63000001 63100045 63100167 78200410 78201000		GUARDRAIL MARKERS TYPE A	TERMINAL MARKERS DIRECT APPLIED
		SPBGR TYPE A 6' POSTS	TRAF BARRIER TYPE 2		
		FOOT	EACH		
FAP 63 (US 24) - NHS FUNDING					
2169+12.5	2171+69.0	RT	206.5		1
2170+87.5	2171+69.0	LT	69.0	1	2
FAP 63 (US 24) - STP FUNDING					
2171+69.0	2172+50.0	RT	68.5	1	2
2171+69.0	2174+25.0	LT	206.0	1	4
TOTALS			550	2	2

PERMANENT SURVEY MARKERS, TYPE I

66700205		
STATION	DESCRIPTION	EACH
FAP 63 (US 24) - NHS FUNDING		
2154+87.72	POT	1
2155+00.00	POT	1
2164+82.88	POT	1
FAP 63 (US 24) - STP FUNDING		
2178+48.38	POT	1
2178+66.37	POT	1
2187+00.18	POT	1
2186+96.92	POT	1
TOTAL		7