

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				80% FED. 20% STATE ROADWAY 0005
48101200	AGGREGATE SHOULDERS, TYPE B	TON	29.0	29.0
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1.0	1.0
67100100	MOBILIZATION	L SUM	1.0	1.0
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.0	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	1.0
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1.0	1.0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5.0	5.0
70300100	SHORT TERM PAVEMENT MARKING	FOOT	760.0	760.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	50 FT	127.0	127.0
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	2.0	2.0
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	36.0	36.0
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	3197.0	3197.0
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	84.0	84.0
* 78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	351.0	351.0

* SPECIALTY ITEM

FILE NAME *	USER NAME * sparkgw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Default	Default	DRAWN -	REVISED -						302	(34-1,34-2) N	HANCOCK	22	4
	PLOT SCALE * 1/8"=1'-0"	CHECKED -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		
	PLDT DATE * Feb-13-2013 08:44:50AM	DATE -	REVISED -		CONTRACT NO. 72F87								