

Earthwork Schedule
South End of West Field

Station	CUT	CUT	FILL	FILL	ADJUSTED FILL
	END AREA	VOLUME	END AREA	VOLUME	VOLUME (+1.25%)
	(SQ FT)	(CU YD)	(SQ FT)	(CU YD)	(CU YD)
17+00.00	223.9	0	0	0	0
17+50.00	404.4	582	0	0	0
18+00.00	482.3	821	0	0	0
18+50.00	552.5	958	0	0	0
19+00.00	596.6	1064	0	0	0
19+50.00	672.3	1175	0	0	0
20+00.00	686.2	1258	0	0	0
20+50.00	659	1246	0	0	0
21+00.00	613.5	1178	0	0	0
21+50.00	544.8	1073	0	0	0
22+00.00	605.5	1065	0	0	0
22+50.00	567.4	1086	0	0	0
23+00.00	465.4	956	0	0	0
23+50.00	317.3	725	0	0	0
24+00.00	152.2	435	0	0	0
24+50.00	65.9	202	0	0	0
TOTALS	7609	13824	0	0	0

Earthwork Schedule
West Berm of Beaver Pond Ditch

Station	CUT	CUT	FILL	FILL	ADJUSTED FILL
	END AREA	VOLUME	END AREA	VOLUME	VOLUME (+1.25%)
	(SQ FT)	(CU YD)	(SQ FT)	(CU YD)	(CU YD)
27+00.00	0.0	0.0	17.9	0.0	0
27+50.00	0.0	0.0	12.6	28.2	35
28+00.00	0.0	0.0	8.8	19.8	25
28+50.00	0.0	0.0	7.2	14.8	19
29+00.00	0.0	0.0	7.2	13.3	17
29+50.00	0.0	0.0	8.5	14.5	18
30+00.00	0.0	0.0	14.1	20.9	26
30+50.00	0.0	0.0	22.6	34.0	42
31+00.00	0.0	0.0	33.8	52.2	65
31+50.00	0.0	0.0	0.0	31.3	39
32+00.00	0.0	0.0	65.3	60.5	76
32+50.00	0.0	0.0	41.1	98.5	123
33+00.00	0.0	0.0	32.6	68.2	85
33+50.00	0.0	0.0	29.7	57.7	72
34+00.00	0.0	0.0	35.9	60.7	76
34+50.00	0.0	0.0	42.5	72.6	91
35+00.00	0.0	0.0	38.5	75.0	94
35+50.00	0.0	0.0	45.1	77.4	97
36+00.00	0.0	0.0	22.6	62.7	78
36+50.00	0.0	0.0	11.6	31.7	40
TOTALS	0	0	498	894	1119

Earthwork Schedule
East Field

Station	CUT	CUT	FILL	FILL	ADJUSTED FILL
	END AREA	VOLUME	END AREA	VOLUME	VOLUME (+1.25%)
	(SQ FT)	(CU YD)	(SQ FT)	(CU YD)	(CU YD)
27+00.00	0.0	0.0	0.0	0.0	0
27+50.00	174.8	161.9	0.0	0.0	0
28+00.00	177.1	325.8	0.0	0.0	0
28+50.00	171.0	322.3	0.0	0.0	0
29+00.00	162.4	308.7	0.0	0.0	0
29+50.00	168.5	306.4	0.0	0.0	0
30+00.00	186.1	328.3	0.0	0.0	0
30+50.00	191.9	350.0	0.0	0.0	0
31+00.00	190.2	353.8	0.0	0.0	0
31+50.00	287.2	442.0	0.0	0.0	0
32+00.00	93.5	352.5	0.0	0.0	0
32+50.00	0.0	86.6	0.0	0.0	0
TOTALS	17021	3339	0	0	0

Earthwork Schedule
East Berm of Beaver Pond Ditch

Station	CUT	CUT	FILL	FILL	ADJUSTED FILL
	END AREA	VOLUME	END AREA	VOLUME	VOLUME (+1.25%)
	(SQ FT)	(CU YD)	(SQ FT)	(CU YD)	(CU YD)
29+50.00	0.0	0.0	11.0	10.2	13
30+00.00	0.0	0.0	13.0	22.2	28
30+50.00	0.0	0.0	21.7	32.1	40
31+00.00	0.0	0.0	31.3	49.1	61
31+50.00	0.0	0.0	1.9	30.7	38
32+00.00	0.0	0.0	25.0	24.9	31
32+50.00	0.0	0.0	18.7	40.5	51
33+00.00	0.0	0.0	15.2	31.4	39
33+50.00	0.0	0.0	12.5	25.6	32
34+00.00	0.0	0.0	16.3	26.7	33
34+50.00	0.0	0.0	12.7	26.9	34
35+00.00	0.0	0.0	0.0	11.8	15
TOTALS	0	0	179	332	416

Earthwork Schedule
Summary

Location	Earth	Embankment	Total
	Excavation		(Excess)
	(CU YD)	(CU YD)	(CU YD)
West	13824	1119	12705.0
East	3329	416	2913.0
TOTALS	17153	1535	15618

FILE NAME =	USER NAME = teasleyck	DESIGNED -	REVISED -
ct:\pw\work\p\id\teasleyck\d0285341\074557-sh-t-schedules.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = 2/1/2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

EARTH WORK SCHEDULE			
SCALE:	SHEET	OF	SHEETS
	STA.	TO	STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		LAWRENCE	25	5
* 0-7 WETLAND MITIGATION 2013			CONTRACT NO. 74557	
ILLINOIS FED. AID PROJECT				