

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE			
				ROADWAY	ROADWAY	BRIDGE			
				0005 RURAL	0004 RURAL	0014 SN 014-0033			
X0323433	MICROPILE PROOF LOAD TEST	EACH	4	-	-	4			
X0325110	BIAXIAL GEOGRID	SGYD	162	-	-	162			
X5210180	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 550K	EACH	12	-	-	12			
X5860110	GRANULAR BACKFILL FOR STRUCTURES	CU YD	374	-	-	374			
X6660410	REMOVE RIGHT-OF-WAY MARKERS	EACH	2	-	1	1			
X6660445	RIGHT OF WAY AND PROPERTY CORNERS	EACH	7	-	-	7			
Z0004552	APPROACH SLAB REMOVAL	SO YD	195	-	-	195			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	-	-	1			
Z0016702	DETOUR SIGNING	L SUM	1	-	-	1			
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	24	-	-	24			
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	176	-	-	176			
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	-	1	-			
+ Z0076600	TRAINEES	HOUR	3,500	3,500					
Z0064505	SECTION CORNER MARKERS	EACH	7	3	2	2			
+ Z0076609	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	3,500	3,500					
X0327568	TENSION MICROPILES	EACH	48	-	-	48			
X0327569	TENSION MICROPILE LOAD TEST	EACH	4	-	-	4			

+0042

△ REVISED 4/8/13



USER NAME *	DESIGNED - JWH	REVISED -
PLOT SCALE *	DRAWN - PRC	REVISED -
PLOT DATE * 2/1/2013	CHECKED - RLM	REVISED -
	DATE - 2/1/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
STRUCTURE NO. 014-0033

SCALE: SHEET 9 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
42	1-IBR-2	CLINTON	159	11
ILLINOIS FED. AID PROJECT			CONTRACT NO. 76479	