

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE			
				ROADWAY	ROADWAY	BRIDGE			
				0005	0004	0014			
				RURAL	RURAL	SN 014-0033			
52000110	PREFORMED JOINT STRIP SEAL	FOOT	38	-	-	38			
52000208	FINGER PLATE EXPANSION JOINT, 3"	FOOT	36	-	-	36			
52000212	FINGER PLATE EXPANSION JOINT, 4"	FOOT	36	-	-	36			
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	84	-	-	84			
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	24	-	-	24			
52100520	ANCHOR BOLTS, 1"	EACH	72	-	-	72			
52100530	ANCHOR BOLTS, 1-1/4"	EACH	36	-	-	36			
52100540	ANCHOR BOLTS, 1-1/2"	EACH	12	-	-	12			
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	86	-	38	48			
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	16	-	-	16			
54213453	END SECTIONS 18"	EACH	8	-	2	6			
58700300	CONCRETE SEALER	SQ FT	2128	-	-	2128			
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	179	-	-	179			
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	537.5	-	-	537.5			



USER NAME *	DESIGNED - JMH	REVISED -
PLOT SCALE *	DRAWN - PRC	REVISED -
PLOT DATE * 2/1/2013	CHECKED - RLM	REVISED -
	DATE - 2/1/2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
STRUCTURE NO. 014-0033**

SCALE: SHEET 5 OF 9 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
42	I-18R-2	CLINTON	159	7
CONTRACT NO. 76479			ILLINOIS FED. AID PROJECT	