

PAVEMENT MARKING SCHEDULE CONTINUED																											
LOCATION					YELLOW SHORT TERM PAVEMENT MARKING DOUBLE CL (FOOT)	YELLOW SHORT TERM PAVEMENT MARKING SKIP DASH (FOOT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ.FT)	THERMOPLASTIC PAVEMENT MARKING LETTERS AND SYMBOLS (SQ.FT)	WHITE THERMOPLASTIC PAVEMENT MARKING LINE 4" (FOOT)	YELLOW THERMOPLASTIC PAVEMENT MARKING LINE 4" (FOOT)	YELLOW THERMOPLASTIC PAVEMENT MARKING SKIP-DASH 4" (FOOT)	YELLOW THERMOPLASTIC PAVEMENT MARKING DOUBLE CL 4" (FOOT)	WHITE THERMOPLASTIC PAVEMENT MARKING DOTTED 4" (FOOT)	WHITE THERMOPLASTIC PAVEMENT MARKING LINE 8" (FOOT)	WHITE THERMOPLASTIC PAVEMENT MARKING LINE 12" (FOOT)	YELLOW THERMOPLASTIC PAVEMENT MARKING LINE 12" (FOOT)	WHITE THERMOPLASTIC PAVEMENT MARKING LINE 24" (FOOT)	PAINT PAVEMENT MARKING LETTERS AND SYMBOLS (SQ.FT)	PAINT PAVEMENT MARKING LINE 6" (FOOT)	WHITE MOD. URETHANE PAVEMENT MARKING LINE 4" (FOOT)	YELLOW MOD. URETHANE PAVEMENT MARKING LINE 4" (FOOT)	YELLOW MOD. URETHANE PAVEMENT MARKING SKIP-DASH 4" (FOOT)	RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) (EACH)	PAVEMENT REMOVAL (SQ.FT)	RAISED REFLECTIVE PAVEMENT MARKING REMOVAL (EACH)	
ALI	STATION	TO	STATION	OFFSET																							
PR IL 127	127+00.00	TO	128+03.60	RT				103.60																			
PR IL 127	127+00.00	TO	128+91.04	LT				191.04																			
PR IL 127	127+00.00	TO	128+91.04	CL					191.04	47.75												5					
PR IL 127	128+91.04	TO	141+18.54	CL																	1227.50	1227.50	306.88		31		
PR IL 127	128+91.04	TO	141+18.54	LT																	1227.50						
PR IL 127	128+91.04	TO	141+18.54	RT																			17				
PR IL 127	141+18.54	TO	147+85.00	CL																							
PR IL 127	141+18.54	TO	147+85.00	LT				662.83																			
PR IL 127	141+18.54	TO	143+01.45	RT				183.51																			
PR IL 127	141+18.79	TO	142+00.00	CL						20.30																	
PR IL 127	142+00.00	TO	146+37.63	CL							875.26																
PR IL 127	144+14.22	TO	147+85.00	RT				372.78																			
PR IL 127	146+37.63	TO	147+85.00	CL						36.84																	
SUBTOTAL					3516	499	1339	124	63108	24426	2714	5235	28	293	74	85	138	5	192	2455	1228	307	823	31	257	767	
TOTAL					4016		1339	124			95512				293	159	138	5	192		3990		823	31	257	767	

PIPE CULVERT SCHEDULE								
LOCATION					PIPE CULVERT REMOVAL (FEET)	PIPE CULVERTS, CLASS A, TYPE 1 18" (FEET)	PIPE CULVERTS, CLASS D, TYPE 1 18" (FEET)	END SECTIONS 18" (EACH)
ALI	STATION	OFFSET	TO STATION	OFFSET				
PR PRKNRIDE	10+26.33	CL	10+27.84	CL	43			
PR PRKNRIDE	10+30.46	LT	10+24.40	RT		38	2	
PR JON RD	5+81.30	RT	5+98.22	RT			16	
PR JON RD	6+50.00	LT	6+50.00	RT		23	2	
PR IL 127	128+76.04	RT	129+12.04	N/A				
PR IL 127	145+31.99	LT	145+57.09	LT		25	2	
TOTAL					43	86	16	8

SUBTOTAL SUMMATION			
SUBTOTALS FROM SCHEDULE	BITUMINOUS MATERIALS (PRIME COAT) (TON)	HOT - MIX ASPHALT SURFACE COURSE, MIX "C", N70 (TON)	INCIDENTAL HMA SURFACING (TON)
ENTRANCE SCHEDULE	1.00		67.00
MAILBOX SCHEDULE	0.15		10.00
PAVEMENT SCHEDULE	20.00	636.0	
RESURFACING SCHEDULE	79.03	10316.0	
SIDEROAD SCHEDULE	2.00		229.00
TOTAL	103	10952	306

MISCELLANEOUS SCHEDULES									
LOCATION	ENGINEER'S FIELD OFFICE, TYPE A (CAL MO)	MOBILIZATION (L SUM)	TRAFFIC CONTROL AND PROTECTION STANDARD, 701201 (L SUM)	TRAFFIC CONTROL AND PROTECTION STANDARD, 701206 (L SUM)	TRAFFIC CONTROL AND PROTECTION STANDARD, 701306 (L SUM)	CHANGEABLE MESSAGE SIGN (CAL MO)	CONSTRUCTION LAYOUT (L SUM)	DETOUR SIGNING (L SUM)	RAILROAD PROTECTIVE LIABILITY INSURANCE (L SUM)
JOBSITE	30	1	1	1	1	100	1	1	1
TOTAL	30	1	1	1	1	100	1	1	1

E:\10241\Plan_Sheets\0876479-plt-schedule.dgn