

EROSION CONTROL SCHEDULE CONTINUED													
LOCATION					SEEDING, CLASS 2A (ACRE)	MULCH, METHOD 2 (ACRE)	EROSION CONTROL BLANKET (SQ YD)	HEAVY DUTY EROSION CONTROL BLANKET (SQ YD)	TEMPORARY DITCH CHECKS (FOOT)	PERIMETER EROSION BARRIER (FOOT)	INLET AND PIPE PROTECTION (EACH)	STONE RIPRAP, CLASS A5 (SQ YD)	FILTER FABRIC (SQ YD)
ALI	STATION	TO	STATION	OFFSET									
PR IL 127	143+98.76	TO	145+50.07	RT	0.04		186.67						
PR IL 127	144+50.00	TO	N/A	LT				12					
PR IL 127	144+50.00	TO	N/A	RT				12					
PR IL 127	145+29.58	TO	147+82.82	RT	0.06	0.06							
PR IL 127	145+29.58	TO	147+51.35	RT	0.03		157.67						
PR IL 127	145+50.00	TO	N/A	RT				12					
PR IL 127	145+50.60	TO	147+82.82	LT	0.10	0.10							
PR IL 127	145+62.00	TO	N/A	LT						1			
PR IL 127	146+50.00	TO	N/A	LT				12					
PR IL 127	146+50.00	TO	N/A	RT				12					
PR IL 127	147+50.00	TO	N/A	LT				12					
PR IL 127	147+50.00	TO	N/A	RT				12					
TOTAL					3.50	2.25	1688	1749	360	4601	5	199	199

FERTILIZER SCHEDULE			
LOCATION	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)
PR SLANT RD	90	90	90
PR IL 127 & PR JON RD	225	225	225
TOTAL	315	315	315

TEMPORARY SEEDING SCHEDULE	
LOCATION	TEMPORARY EROSION CONTROL SEEDING (POUND)
PR SLANT RD	400
PR IL 127 & PR JON RD	1000
TOTAL	1400

E:\1024\Plan_Sheets\0876479-11t-spp-sched.dgn



USER NAME = Plotted by Scott	DESIGNED - RC	REVISED -
	DRAWN - RC	REVISED -
PLOT SCALE = 2.0000' / in.	CHECKED - SEW	REVISED -
PLOT DATE =	DATE - 2-1-2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

STORM WATER POLLUTION & PREVENTION PLAN SUMMARY OF SCHEDULES		
SCALE: N/A	SHEET NO. 2 OF 2 SHEETS	STA. N/A TO STA. N/A

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
42	1-1BR-2	CLINTON	159	54
CONTRACT NO. 76479				
ILLINOIS FED. AID PROJECT				