

MICRO-SURFACING SCHEDULE									
STATION		MICRO-SURFACING SINGLE PASS TYPE II	STATION		MICRO-SURFACING SINGLE PASS TYPE II	STATION		MICRO-SURFACING SINGLE PASS TYPE II	
IL 255 - NORTHBOUND		(SQ YD)	IL 255 - SOUTHBOUND		(SQ YD)	POAG RAMP 1		(SQ YD)	
1749+52	TO 1751+68	625	1748+87	TO 1756+03	3103	196+25	TO 216+84	4118	
1751+68	TO 1755+69	1671	1756+03	TO 1774+18	5243	POAG RAMP 2			
1755+69	TO 1774+25	5362	1774+18	TO 1775+19	488	300+43	TO 382+02	16318	
1774+25	TO 1775+26	511	1775+19	TO 1777+41	BRIDGE OMISSION	POAG RAMP 3			
1775+26	TO 1777+48	BRIDGE OMISSION	1777+41	TO 1778+20	250	309+37	TO 324+80	3086	
1777+48	TO 1783+76	2303	1778+20	TO 1785+49	2106	POAG RAMP 4			
1783+76	TO 1785+76	578	1785+49	TO 1789+75	BRIDGE OMISSION	455+70	TO 474+64	3788	
1785+76	TO 1790+02	BRIDGE OMISSION	1789+75	TO 1815+75	7511	474+64	TO 476+53	462	
1790+02	TO 1815+80	7448	1815+75	TO 1816+94	BRIDGE OMISSION	MADISON AVE RAMP 1			
1815+80	TO 1816+99	BRIDGE OMISSION	1816+94	TO 1834+83	5168	11+40	TO 32+00	4120	
1816+99	TO 1835+87	5454	1834+83	TO 1838+17	BRIDGE OMISSION	MADISON AVE RAMP 2			
1835+87	TO 1839+21	BRIDGE OMISSION	1838+17	TO 1847+85	2796	14+03	TO 30+24	3242	
1839+21	TO 1847+85	2496	1847+85	TO 1848+73	BRIDGE OMISSION	30+24	TO 33+06	689	
1847+85	TO 1848+73	BRIDGE OMISSION	1848+73	TO 1865+01	4703	MADISON AVE RAMP 3			
1848+73	TO 1872+71	6928	1865+01	TO 1875+21	4023	11+36	TO 25+28	2784	
1872+71	TO 1876+90	1723	1875+21	TO 1893+83	5379	MADISON AVE RAMP 4			
1876+90	TO 1894+90	5200	1893+83	TO 1895+10	642	13+30	TO 30+00	3340	
1894+90	TO 1895+10	101	1895+10	TO 1897+15	BRIDGE OMISSION	30+00	TO 32+91	711	
1895+10	TO 1897+15	BRIDGE OMISSION	1897+15	TO 1898+04	282	IL 143 RAMP 1			
1897+15	TO 1904+90	2885	1898+04	TO 1929+27	9022	11+67	TO 28+90	1723	
1904+90	TO 1928+06	6691	1929+27	TO 1936+28	2492	IL 143 RAMP 2			
1928+06	TO 1931+05	1063	1936+28	TO 1950+28	5911	13+40	TO 19+00	1618	
1931+05	TO 1946+05	6333	1950+28	TO 1954+30	1854	19+00	TO 20+67	594	
1946+05	TO 1949+46	1781	1954+30	TO 1964+37	2909				
1949+46	TO 1963+25	3984							
SUBTOTAL		63137			63882			46593	
TOTAL					173612				

AGGREGATE SHOULDERS					
LOCATION		LENGTH	WIDTH	TYPE A, 6"	
STA	TO STA	(FT)	(FT)	(SQ YD)	
POAG RD RAMP 1 - RIGHT					
14+30	TO 17+30	300.0	3.0	100	
MADISON AVE RAMP 1 - RIGHT					
196+25	TO 201+60	535.0	3.0	178	
TOTAL:					278

PARTIAL DEPTH PATCHING						
LOCATION	LANE	LENGTH	WIDTH	BITUMINOUS MATERIALS (PRIME COAT)	PARTIAL DEPTH REM 2 INCH	HMA PART. DEPTH PATCHING
		(FT)	(FT)	(TON)	(SQ. YD.)	(TON)
IL 255 NB						
1941+75	OUTSIDE	20.0	2.0	0.001	4	0.5
1950+00	OUTSIDE	200.0	2.0	0.014	44	5.0
IL 255 SB						
1748+87	OUTSIDE	2.0	22.0	0.002	5	0.5
1777+41	OUTSIDE	2.0	17.0	0.001	4	0.4
1785+39	OUTSIDE	10.0	12.0	0.004	13	1.5
1815+73	OUTSIDE	2.0	12.0	0.001	3	0.3
1816+94	OUTSIDE	2.0	12.0	0.001	3	0.3
POAG RD RAMP 1						
210+50	OUTSIDE	12.0	2.0	0.001	3	0.3
211+00	OUTSIDE	4.0	2.0	0.000	1	0.1
SUBTOTAL:				0.025	80	8.9
ANTICIPATED FAILURES (15%):				0.004	12	1.3
TOTAL:				0.03	92	10.3

RAISED REFLECTIVE PAVEMENT MARKERS				
LOCATION			ONE WAY CRYSTAL	REMOVAL
STA	TO STA	STA	(EACH)	(EACH)
IL 255 - NORTHBOUND				
1749+52	TO 1775+26		66	66
1777+48	TO 1785+76		24	24
1790+02	TO 1815+80		64	64
1816+99	TO 1835+87		48	48
1839+21	TO 1847+85		22	22
1848+73	TO 1895+10		116	116
1897+15	TO 1963+25		166	166
IL 255 - SOUTHBOUND				
1748+87	TO 1775+19		74	74
1777+41	TO 1785+49		20	20
1789+75	TO 1815+75		66	66
1816+94	TO 1834+83		44	44
1838+17	TO 1847+85		24	24
1848+73	TO 1895+10		130	130
1897+15	TO 1964+37		212	212
POAG RAMP 2				
282+02	TO 285+50		26	26
POAG RAMP 4				
455+70	TO 459+00		43	43
MADISON AVE RAMP 2				
14+03	TO 17+20		38	38
MADISON AVE RAMP 4				
13+30	TO 16+50		53	53
IL 143 RAMP 2				
13+40	TO 16+60		49	49
TOTAL			1285	1285