

# SUMMARY OF QUANTITIES

COUNTY:	WILLIAMSON
FUNDING:	100% STATE
LOCATION:	URBAN
ROUTE:	FAP 331 IL 13
	ROADWAY 0001

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0001
20100110	TREE REMOVAL ( 6 TO 15 UNITS DIAMETER)	UNIT	190	190
20100210	TREE REMOVAL ( OVER 15 UNITS DIAMETER)	UNIT	343	343
20200100	EARTH EXCAVATION	CU YD	3180	3180
20400100	BORROW EXCAVATION	CU YD	26260	26260
20800150	TRENCH BACKFILL	CU YD	901	901
20900110	POROUS GRANULAR BACKFILL	CU YD	83	83
* 25000305	SEEDING, CLASS 3A	ACRE	4.25	4.25
* 25000350	SEEDING, CLASS 7	ACRE	3.00	3.00
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	384	384
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	384	384
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	384	384
* 25100115	MULCH, METHOD 2	ACRE	4.25	4.25
* 25100630	EROSION CONTROL BLANKET	SQ YD	2749	2749
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	850	850
28000305	TEMPORARY DITCH CHECKS	FOOT	264	264
28000400	PERIMETER EROSION BARRIER	FOOT	1772	1772
28000500	INLET AND PIPE PROTECTION	EACH	21	21
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	78	78

\* SPECIALTY ITEM