

# SUMMARY OF QUANTITIES

|           |                  |
|-----------|------------------|
| COUNTY:   | WILLIAMSON       |
| FUNDING:  | 100% STATE       |
| LOCATION: | URBAN            |
| ROUTE:    | FAP 331<br>IL 13 |

| CODE NUMBER | ITEM DESCRIPTION                             | UNIT   | TOTAL QUANTITY | ROADWAY |
|-------------|--|--------|----------------|---------|
|             |  |        |                | 0001    |
| 30200650    | PROCESSING MODIFIED SOIL 12"                 | SQ YD  | 8361           | 8361    |
| 31001500    | LIME   | TON    | 206.9          | 206.9   |
| 35100300    | AGGREGATE BASE COURSE, TYPE A 4"             | SQ YD  | 160            | 160     |
| 35100700    | AGGREGATE BASE COURSE, TYPE A 8"             | SQ YD  | 7458           | 7458    |
| 40200500    | AGGREGATE SURFACE COURSE, TYPE A 6"          | SQ YD  | 258            | 258     |
| 40600100    | BITUMINOUS MATERIALS (PRIME COAT)            | GALLON | 683            | 683     |
| 40600300    | AGGREGATE (PRIME COAT)                       | TON    | 11             | 11      |
| 40603090    | HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90  | TON    | 1035           | 1035    |
| 40603315    | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70 | TON    | 616            | 616     |
| 40800050    | INCIDENTAL HOT-MIX ASPHALT SURFACING         | TON    | 19             | 19      |
| 42001300    | PROTECTIVE COAT                              | SQ YD  | 677            | 677     |
| 40201000    | AGGREGATE FOR TEMPORARY ACCESS               | TON    | 313            | 313     |
| 42400300    | PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH     | SQ FT  | 22363          | 22363   |
| 42400800    | DETECTABLE WARNINGS                          | SQ FT  | 53             | 53      |
| 44000600    | SIDEWALK REMOVAL                             | SQ FT  | 289            | 289     |
| 48100700    | AGGREGATE SHOULDERS, TYPE A 8"               | SQ YD  | 1707           | 1707    |
| 50105220    | PIPE CULVERT REMOVAL                         | FOOT   | 20             | 20      |
| 542A1069    | PIPE CULVERTS, CLASS A, TYPE 2 24"           | FOOT   | 251            | 251     |
| 542A1081    | PIPE CULVERTS, CLASS A, TYPE 2 36"           | FOOT   | 91             | 91      |
| 542D0220    | PIPE CULVERTS, CLASS D, TYPE 1 15"           | FOOT   | 84             | 84      |