CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 80% FEDERAL 20% STATE ROADWAY 0003 RURAL
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	14893	14893
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX E, N105	TON	15	15
40701941	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13"	SQ YD	9599	9599
44000100	PAVEMENT REMOVAL	SQ YD	1989	1989
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1½"	SQYD	172	172
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	111	111
44004250	PAVED SHOULDER REMOVAL	SQ YD	2824	2824
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SQ YD	5497	5497
48301000	PROTECTIVE COAT	SQ YD	126	126
54248510	CONCRETE COLLAR	CU YD	0.21	0.21
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	95	95
60260100	INLETS TO BE ADJUSTED	EACH	1	1
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	22	22
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	143	143
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	670	670
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3