

CODE NUMBER	PAY ITEM	CONSTRUCTION TYPE CODE 0014	
		UNIT	STATE FUNDING 50% ILLINOIS & 50% KENTUCKY SN 064-0035
70400100	TEMPORARY CONCRETE BARRIER	FOOT	5125
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	5125
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	6
* 70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4
* 70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	6
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	26156
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	149
78300100	PAVEMENT MARKING REMOVAL	SQ FT	8046
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	149
X0322556	STIFFENER INTERSECTION MODIFICATION	EACH	2
X5090098	REPLACE HANDRAIL SUPPORT	EACH	33
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	23,410

*SPECIALTY ITEM

FILE NAME =	USER NAME = h01st00d1w	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\h01st00d1w\d832680217	293-shl-plan.dgn	DRAWN -	REVISED -						24	BSMART 2013-1	MASSAC	23	4
Default	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -		SCALE: SHEET OF SHEETS STA. TO STA.				CONTRACT NO. 78293				
	PLOT DATE = 2/1/2013	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								