




PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	PAINT PAVEMENT MARKING		
	4 INCH		24 INCH
	WHITE	YELLOW	WHITE
	FOOT	FOOT	FOOT
<b>IL 127</b>			
STA 9+91 TO STA 11+05 (SKIP DASH)		30	
STA 9+95 TO STA 10+06 (PARKING LINES)	40		
STA 10+25 (STOP BAR)			17
<b>SUBTOTAL</b>	<b>40</b>	<b>30</b>	<b>17</b>

SIDEWALK SCHEDULE

LOCATION STATION TO STATION	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	PORTLAND CEMENT CONCRETE SIDEWALK, 6"	SIDEWALK REMOVAL
	SQ FT	SQ FT	SQ FT
<b>ILLINOIS 127</b>			
STA 10+07.5 RT TO STA 11+05 RT	646		837
STA 10+14 LT TO STA 10+19 LT		75	
STA 10+08 LT TO STA 10+30 LT	200		274
<b>TOTALS</b>	<b>846</b>	<b>75</b>	<b>1,111</b>

DETOUR ROUTE SIGN SCHEDULE

SIGN ID NO.	DESCRIPTION	NUMBER REQUIRED EACH	SIGN SIZE	SIGN PANEL TYPE 1 SQ FT	SIGN PANEL TYPE 2 SQ FT
M4-9R	DETOUR	13	24" x 12"	26	
M1-I100	127	13	24" x 24"	52	
M6-1		5	21" x 15"	10.9	
M6-1L		5	21" x 15"	10.9	
M6-3		3	21" x 15"	6.6	
W20-2	DETOUR AHEAD	6	48" x 48"		96
	TRUCKS ONLY	19	24" x 24"	76	
<b>TOTALS</b>				<b>182.4</b>	<b>96</b>