

LOCATION OF WORK
 F. A. I. ROUTE 57 (1-57)
 STA. 166+50 TO 147+00, WILLIAMSON COUNTY
 FUNDING BREAKOUT 90% FEDERAL 10% STATE

LOCATION OF WORK
 F. A. I. ROUTE 57 (1-57)
 STA. 166+50 TO 147+00, WILLIAMSON COUNTY
 FUNDING BREAKOUT 90% FEDERAL 10% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE	
				0003 RURAL	0013 RURAL	0003 RURAL	0013 RURAL
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	12	12			
54248510	CONCRETE COLLAR	CU YD	9.44	9.44			
55200900	STORM SEWERS JACKED IN PLACE 24"	FOOT	90	90			
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	566			566	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	81	81			
60107600	PIPE UNDERDRAINS 4"	FOOT	42743	42743			
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	2305	2305			
60500050	REMOVING CATCH BASINS	EACH	1	1			
60500060	REMOVING INLETS	EACH	19	19			
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	4	4			
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	3737.5	3737.5			
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	13	13			
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	5	5			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6			

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY		BRIDGE	
				0003 RURAL	0013 RURAL	0003 RURAL	0013 RURAL
* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	3	3			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	17	17			
63200310	GUARDRAIL REMOVAL	FOOT	3641	3641			
63500105	DELINEATORS	EACH	14	14			
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	47459	47459			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	24	24			
67100100	MOBILIZATION	L SUM	1	1			
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	730	730			
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1			
* 70300100	SHORT TERM PAVEMENT MARKING	FOOT	7000	7000			
* 70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	243323	243323			
* 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	52625	52625			
* 70300530	PAVEMENT MARKING TAPE, TYPE III 5"	FOOT	15000	15000			

* SPECIALTY ITEM

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILEL#	#USER#	- JRD	-			57	011-6-2,X1-5,X11-4-1BR-1HR-1	WILLIAMSON	202	6	
		DRAWN	REVISED			SCALE: N, T, S. SHEET NO. 3 OF 5 SHEETS		CONTRACT NO. 78334		ILLINOIS FED. AID PROJECT	
		- MSK	-			STA. TO STA.					
		CHECKED	REVISED								
		- SLD	-								
		DATE	REVISED								
		- 02/01/2013	-								