

**SUMMARY OF QUANTITIES
CONSTRUCTION TYPE CODE: 0004**

Item No.	Pay Item	Unit	Quantities		
			Total	PARTICIPATING	NON PARTICIPATING
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	423.0	423.0	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1329.0	1329.0	
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	149.0	149.0	
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	149.0	149.0	
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	149.0	149.0	
20200100	EARTH EXCAVATION	CU YD	5571.6	5571.6	
20800150	TRENCH BACKFILL	CU YD	1700.1	1700.1	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	13919.0	13919.0	
21101600	TOPSOIL FURNISH AND REPLACE, VARIABLE DEPTH	SQ YD	450.0	450.0	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	12019.6	12019.6	
25200110	SODDING, SALT TOLERANT	SQ YD	12019.6	12019.6	
25200200	SUPPLEMENTAL WATERING	UNIT	504.8	504.8	
28000400	PERIMETER EROSION BARRIER	FOOT	100.3	100.3	
28000500	INLET AND PIPE PROTECTION	EACH	40.0	40.0	
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	13919.0	13919.0	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	3345.9	3345.9	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	20.6	20.6	
42001300	PROTECTIVE COAT	SQ YD	17434.7	17434.7	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1755.3	1755.3	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	23578.0	23578.0	
42400800	DETECTABLE WARNINGS	SQ FT	383.0	383.0	
44000100	PAVEMENT REMOVAL	SQ YD	10857.1	10857.1	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1917.7	1917.7	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	9171.4	9171.4	
44000600	SIDEWALK REMOVAL	SQ FT	19374.2	19374.2	
50300225	CONCRETE STRUCTURES	CU YD	4.1	4.1	
50800105	REINFORCEMENT BARS	POUND	104.2	104.2	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	899.0	899.0	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	779.0	779.0	
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	397.0	397.0	
550A0400	STORM SEWERS, CLASS A, TYPE 2 21"	FOOT	625.0	625.0	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	262.0	262.0	
55100500	STORM SEWER REMOVAL 12"	FOOT	305.0	305.0	
56100005	DUCTILE IRON WATER MAIN TEE, 6" X 6"	EACH	3.0		3.0
56100015	DUCTILE IRON WATER MAIN TEE, 8" X 6"	EACH	9.0		9.0
56100020	DUCTILE IRON WATER MAIN TEE, 8" X 8"	EACH	1.0		1.0
56100045	DUCTILE IRON WATER MAIN TEE, 12" X 4"	EACH	1.0		1.0
56100500	WATER MAIN 4"	FOOT	30.0		30.0
56100600	WATER MAIN 6"	FOOT	603.0		603.0
56100700	WATER MAIN 8"	FOOT	1473.0		1473.0
56101150	DUCTILE IRON WATER MAIN REDUCER, 8" X 6"	EACH	2.0		2.0
56108800	TAPPING VALVES AND SLEEVES 6"	EACH	2.0		2.0
56109418	DUCTILE IRON WATER MAIN FITTINGS 6" 45.00 DEGREE BEND	EACH	2.0		2.0
56109420	DUCTILE IRON WATER MAIN FITTINGS 8" 45.00 DEGREE BEND	EACH	2.0		2.0
56109434	DUCTILE IRON WATER MAIN FITTINGS 8" 90.00 DEGREE BEND	EACH	1.0		1.0
56200300	WATER SERVICE LINE 1"	FOOT	2120.0		2120.0
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1.0		1.0
56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	1.0		1.0
56400820	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	6.0		6.0
60107600	PIPE UNDERDRAIN 4"	FOOT	4858.0		4858.0
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2.0		2.0
60224469	MANHOLES, TYPE A, 9'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2.0		2.0
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	7.0		7.0
60255500	MANHOLES TO BE ADJUSTED	EACH	7.0		7.0
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1.0		1.0
60500060	REMOVING INLETS	EACH	9.0		9.0
60600605	CONCRETE CURB, TYPE B	FOOT	454.0		454.0
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6,24	FOOT	37.0		37.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12.0		12.0
67100100	MOBILIZATION	L SUM	1.0		1.0
70300210	TEMPORARY PAVEMENT MARKING, LETTERS AND SYMBOLS	SQ FT	31.2		31.2
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	433.5		433.5
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	458.9		458.9
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	29.3		29.3
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	326.2		326.2
78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	93.6		93.6
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3060.4		3060.4
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	1339.0		1339.0
78001140	PAINT PAVEMENT MARKING - LINE 8"	FOOT	448.6		448.6
78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	257.1		257.1
78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	103.8		103.8
81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	16.0		16.0
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	425	425	
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	

Item No.	Pay Item	Unit	Quantities		
			Total	PARTICIPATING	NON PARTICIPATING
81028360	UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	14.0	14.0	
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	21.0	21.0	
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	134.0	134.0	
81400100	HANDHOLE	EACH	1.0	1.0	
88600100	DETECTOR LOOP, TYPE I	FOOT	208.0	208.0	
89502380	REMOVE EXISTING HANDHOLE	EACH	1.0	1.0	
A2000118	TREE, ACER X FREEMANII AUTUMN BLAZE (AUTUMN BLAZE FREEMAN MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	19.0	19.0	
A2000220	TREE, ACER X FREEMANII MARMO (MARMO FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	12.0	12.0	
A2005520	TREE, NYSSA SYLVATICA (BLACK TUPELO), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	15.0	15.0	
A2006520	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	13.0	13.0	
A2007120	TREE, QUERCUS RUBRA (RED OAK), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	23.0	23.0	
A2007674	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 10' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	3.0	3.0	
B2000766	TREE, AMELANCHIER X GRANDIFLORA AUTUMN BRILLIANCE (AUTUMN BRILLIANCE SERVICE BERRY), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	18.0	18.0	
B2013468	TREE, MALUS GOLDEN RAINDROPS (GOLDEN RAINDROPS CRABAPPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5.0	5.0	
C2007865	SHRUB, ROSA X KNOCK OUT (KNOCK OUT ROSE), CONTAINER GROWN, 5-GALLON	EACH	78.0	78.0	
D2001984	EVERGREEN, PICEA GLAUCA DENSATA (BLACK HILLS SPRUCE), 7' HEIGHT, BALLED AND BURLAPPED	EACH	7.0	7.0	
K0012990	PERENNIAL PLANTS, ORNAMENTAL TYPE, GALLON POT	UNIT	21.6	21.6	
K0012995	PERENNIAL PLANTS - ORNAMENTAL GRASS TYPE, 5-GALLON POT	UNIT	1.1	1.1	
K0029634	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	100.0	100.0	
K1001988	IRRIGATION SYSTEM SPECIAL	L SUM	1.0	1.0	
K1005481	SHREDED BARK MULCH, 3"	SQ YD	450.0	450.0	
LR420100	PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL) WITH INTEGRAL CURB	SQ YD	12969.0	12969.0	
X0323449	REMOVE EXISTING WATER VALVE	EACH	7.0		7.0
X0326712	ABANDON AND FILL EXISTING SANITARY SEWER	EACH	10.0		10.0
X0327077	REMOVE CURB STOP BOX	EACH	42.0		42.0
X0327078	REMOVE FIRE HYDRANT AND VALVE ASSEMBLY	EACH	2.0		2.0
X0327368	SANITARY SEWER, DUCTILE IRON, 12"	FOOT	1572.0		1572.0
X0327369	SANITARY SEWER, DUCTILE IRON, 10"	FOOT	121.0		121.0
X5610009	PIPE INSULATION SYSTEM	FOOT	280.0		280.0
X5610746	WATER MAIN LINE STOP 6"	EACH	2.0		2.0
X5622402	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID, SPECIAL	EACH	11.0		11.0
X5623102	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID, SPECIAL	EACH	3.0		3.0
X6024240	INLETS, SPECIAL	EACH	27.0		27.0
X6028054	SANITARY MANHOLES TO BE REMOVED	EACH	7.0		7.0
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1.0	1.0	
X8950215	RELOCATE EXISTING HANDHOLE	EACH	1.0		1.0
Z0015000	CURB STOPS 1"	EACH	44.0		44.0
Z0056800	SANITARY SEWER 6"	FOOT	3837.0		3837.0
Z0057700	SANITARY SEWER 30"	FOOT	305.0		305.0
Z0077700	WOOD FENCE TO BE REMOVED AND RE-ERECTED	FOOT	235.6	235.6	
XX003528	DUCTILE IRON WATER MAIN FITTING - 8" PLUG	EACH	5.0		5.0
XX003796	TAP & CORP. 1"	EACH	44.0		44.0
XX004289	DUCTILE IRON WATER MAIN FITTING - 6" PLUG	EACH	5.0		5.0
XX006077	GATE VALVE & BOX 6"	EACH	3.0		3.0
XX006241	GATE VALVE & BOX 8"	EACH	8.0		8.0
XX006467	WYE BRANCHES, 12" x 6"	EACH	58.0		58.0
XX007263	GATE VALVE & BOX 4"	EACH	1.0		1.0
XX008214	SANITARY SEWER 16"	FOOT	509.0		509.0
XX008845	SANITARY SEWER SERVICE 30" BEND, 10"	EACH	1.0		1.0
XX008846	SANITARY SEWER SERVICE 45" BEND, 6"	EACH	158.0		158.0
XX008847	SANITARY SEWER SERVICE COUPLING, 6"	EACH	79.0		79.0
XX008848	SANITARY SEWER SERVICE 30" X 6" TEE	EACH	3.0		3.0
XX008849	WYE BRANCHES, 10" X 6"	EACH	1.0		1.0
XX008850	WYE BRANCHES, 16" X 6"	EACH	16.0		16.0
XX008851	DUCTILE IRON WATER MAIN COUPLING, 4"	EACH	1.0		1.0
XX008852	DUCTILE IRON WATER MAIN COUPLING, 6"	EACH	4.0		4.0
XX008853	DUCTILE IRON WATER MAIN CROSS, 8" x 8"	EACH	2.0		2.0
XX008854	DUCTILE IRON WATER MAIN CAP, 6"	EACH	6.0		6.0
XX008855	DUCTILE IRON WATER MAIN CAP, 8"	EACH	1.0		1.0
XX008856	WATER MAIN DOUBLE LINE STOP 6"	EACH	5.0		5.0
XX008857	CRUSHED STONE TRENCH FOUNDATION	TON	50.0		50.0
66900530	SOIL DISPOSAL ANALYSES	EACH	3	3	
	FUND CODE 0042 :				
Z0076800	TRAINEES	HOURS	500.0	500.0	
Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOURS	500.0	500.0	

Δ SPECIALTY ITEMS

Δ Revised 4/15/13

REVISIONS	DESCRIPTION	DATE
No.		

Missman, Inc.
 Professional Engineers & Land Surveyors
 Rock Island, IL • Belvidere, IL • Rockford, IL • Sycamore, IL
 (815) 344-0260 (815) 955-5400 (815) 955-3825
 www.missman.com

STATE STREET RE-CONSTRUCTION
 GENESEO, ILLINOIS
SUMMARY OF QUANTITIES

Missman Project No:
 A10M008
 File Name:
 A10M008 SUMMARY OF QUANTITIES
 © COPYRIGHT 2013
 ALL RIGHTS RESERVED
 Drawn By: WKS
 Checked By: JLM
 Date: May, 2012