

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
MULTIPLE	12-00177-02-SP	PEORIA	66	2
FED. ROAD DIST. NO.	---	ILLINOIS	PROJECT: HSIP 0143 (052)	
CONTRACT NO. 89627				

SUMMARY OF QUANTITIES					
CODE NO	ITEM	UNIT	QUANTITY	CONST. TYPE CODE	
67100100	MOBILIZATION	L SUM	1	1	
72000100	SIGN PANEL - TYPE 1	SQ FT	3882	3882	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	8430	8430	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	



CHEVRON SIGN
W1-8 18"x24"



POST STRIP SIGN
2"x48"

SIGN PANEL - TYPE 1 SUMMARY				
SIGN NAME	SIGN CODE	SIGN QUANTITY	UNIT AREA SQ FT	TOTAL SQ FT
CHEVRON	W1-8	1054	3.00	3162
BIDIRECTIONAL ARROW	W1-7	1	8.00	8
DIRECTIONAL ARROW	W1-6R	1	8.00	8
POST STRIP		1056	0.67	704

SIGN QUANTITY SUMMARY				
	SIGN QUANTITY	SQ FT	POST QUANTITY	FOOT
PEORIA COUNTY	548	1654	306	4590
WOODFORD COUNTY	508	1524	256	3840
TOTAL	1056	3178	562	8430

GENERAL NOTES:

- ALL CHEVRON SIGNS (W1-8) SHALL BE DIMENSIONED AS 18"x24" (3.00 SQUARE FEET)
- EACH CHEVRON SIGN SHALL BE ACCOMPANIED BY A SOLID YELLOW POST STRIP SIGN OF THE SAME MATERIAL DIMENSIONED AS 2"x48" (0.67 SQUARE FEET)
- ALL SIGNS SHALL BE PLACED IN EXISTING LOCATIONS OR IN LOCATIONS SPECIFIED IN THE PLANS OR AS DIRECTED BY THE ENGINEER.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CONSTRUCTION LAYOUT. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST OF THE CONTRACT.
- PROPOSED POST LENGTHS, AS PER THE SCHEDULE OF QUANTITIES, SHALL BE MODIFIED TO FIT FIELD CONDITIONS AS DIRECTED BY THE ENGINEER.
- ALL NEW SIGNS PANELS SHALL INCLUDE THE YEAR OF MANUFACTURE AND THE INITIALS "PCHD" FOR THOSE INSTALLED IN PEORIA COUNTY AND "WCHD" FOR THOSE INSTALLED IN WOODFORD COUNTY. THESE INITIALS SHALL BE AT THE BOTTOM FACE OF EACH SIGN TO COMPLY WITH FEDERAL SIGN INVENTORY MANAGEMENT GUIDELINES.