

CRUGER TOWNSHIP					
ITEM DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ. FT)	AREA - TY 2 (SQ. FT)
OBJECT MARKER, TY 3 - LEFT	OM3-L	12X36	3	9.00	
OBJECT MARKER, TY 3 - RIGHT	OM3-R	12X36	26	78.00	
STOP	R1-1	30X30	14	87.50	
SPEED LIMIT 25	R2-1	24X30	3	15.00	
WEIGHT LIMIT 8 TONS	R12-1	24X30	1	5.00	
WEIGHT LIMIT 5 TONS / AXLE JAN 15 TO APRIL 15	R12-1104	18X24	15	45.00	
TURN RIGHT	W1-1R	30X30	2	12.50	
CURVE LEFT	W1-2L	30X30	2	12.50	
CURVE RIGHT	W1-2R	30X30	2	12.50	
REVERSE TURN LEFT	W1-3L	30X30	1	6.25	
REVERSE TURN RIGHT	W1-3R	30X30	2	12.50	
REVERSE CURVE LEFT	W1-4L	30X30	2	12.50	
REVERSE CURVE RIGHT	W1-4R	30X30	3	18.75	
ONE DIRECTION LARGE ARROW	W1-6	48X24	5	40.00	
TWO DIRECTION LARGE ARROW	W1-7	48X24	3	24.00	
CHEVRON ALIGNMENT LEFT	W1-8L	18X24	5	15.00	
CHEVRON ALIGNMENT RIGHT	W1-8R	18X24	7	21.00	
CURVE LEFT WITH SIDE ROAD RIGHT	W1-10L	36X36	1	9.00	
CURVE RIGHT WITH SIDE ROAD LEFT	W1-10R	36X36	1	9.00	
STOP AHEAD SYMBOL	W3-1	30X30	13	81.25	
CROSS TRAFFIC DOES NOT STOP	W4-1100	30X18	2	7.50	
GRADE CROSSING ADVANCED WARNING	W10-1	36 DIA	2	18.00	
ADVISORY SPEED (PLAQUE) 15 MPH	W13-1P	18X18	1	2.25	
ADVISORY SPEED (PLAQUE) 20 MPH	W13-1P	18X18	1	2.25	
ADVISORY SPEED (PLAQUE) 25 MPH	W13-1P	18X18	1	2.25	
ADVISORY SPEED (PLAQUE) 30 MPH	W13-1P	18X18	2	4.50	
ADVISORY SPEED (PLAQUE) 40 MPH	W13-1P	18X18	5	11.25	
ADVISORY SPEED (PLAQUE) 45 MPH	W13-1P	18X18	1	2.25	
DEAD END	W14-1	30X30	1	6.25	
			TOTAL	127	0.0

PAY ITEM NUMBER	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY
X7240195	REMOVE EXISTING SIGN PANEL	EACH		128
Z0051398	REMOVE EXISTING SIGN POST	EACH		9
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	108
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH		9
	ASSEMBLY FOR TELESCOPING POST,	EACH		17
72900100	METAL POST, TY A	FOOT	12	0
72900200	METAL POST, TY B	FOOT	12	0
	ASSEMBLY FOR METAL POST,	EACH		72
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	0
	ASSEMBLY FOR WOOD POST,	EACH		43
X7350010	SIGN SUPPORT BRACKET	EACH		3

1. Incidental items. See special provisions.

EL PASO TOWNSHIP					
ITEM DESCRIPTION	MUTCD	SIZE (IN)	NO. OF PIECES	72000100	72000200
				AREA - TY 1 (SQ. FT)	AREA - TY 2 (SQ. FT)
OBJECT MARKER, TY 3 - LEFT	OM3-L	12X36	19	57.00	
OBJECT MARKER, TY 3 - RIGHT	OM3-R	12X36	19	57.00	
OBJECT MARKER, TY 4	OM4-3	18X18	8	18.00	
STOP	R1-1	30X30	12	75.00	
SPEED LIMIT 20	R2-1	24X30	2	10.00	
SPEED LIMIT 30	R2-1	24X30	3	15.00	
SPEED LIMIT 45	R2-1	24X30	3	15.00	
ROAD ENDS	R11-1100	36X30	4	30.00	
WEIGHT LIMIT 5 TONS / AXLE JAN 15 TO APRIL 15	R12-1104	18X24	18	54.00	
SCHOOL BUS STOP AHEAD	S3-1	36X36	1	9.00	
TURN LEFT	W1-1L	30X30	1	6.25	
TURN RIGHT	W1-1R	30X30	3	18.75	
ONE DIRECTION LARGE ARROW	W1-6	48X24	4	32.00	
TWO DIRECTION LARGE ARROW	W1-7	48X24	3	24.00	
CHEVRON ALIGNMENT RIGHT	W1-8R	18X24	1	3.00	
STOP AHEAD SYMBOL	W3-1	30X30	23	143.75	
CROSS TRAFFIC DOES NOT STOP	W4-1100	30X18	12	45.00	
HILL BLOCKS VIEW	W7-6	30X30	5	31.25	
ROAD ENDS 500 FT	W8-1108	30X30	3	18.75	
GRADE CROSSING ADVANCED WARNING	W10-1	36 DIA	2	18.00	
ADVISORY SPEED (PLAQUE) 10 MPH	W13-1P	18X18	2	4.50	
ADVISORY SPEED (PLAQUE) 30 MPH	W13-1P	18X18	1	2.25	
DEAD END	W14-1	30X30	8	50.00	
NO OUTLET	W14-2	30X30	2	12.50	
			TOTAL	159	0.0

PAY ITEM NUMBER	UNIT	SIZE (FT)	NO. OF PIECES	QUANTITY	
X7240195	REMOVE EXISTING SIGN PANEL	EACH		198	
Z0051398	REMOVE EXISTING SIGN POST	EACH		27	
72800100	2"X2" TELESCOPING STEEL SIGN SUPPORT	FOOT	12	0	
73100100	2.25"X2.25" TELESCOPING STEEL SIGN BASE	EACH		0	
	ASSEMBLY FOR TELESCOPING POST,	EACH		0	
72900100	METAL POST, TY A	FOOT	12	0	
72900200	METAL POST, TY B	FOOT	12	0	
	ASSEMBLY FOR METAL POST,	EACH		43	
X7300105	WOOD SUPPORT, 4' X 4'	FOOT	12	0	
X7300105	WOOD SUPPORT, 4' X 6'	FOOT	12	27	324
	ASSEMBLY FOR WOOD POST,	EACH		119	
X7350010	SIGN SUPPORT BRACKET	EACH		4	

1. Incidental items. See special provisions.

DESIGNED - KK	REVISED - KK 04/30/2013
DRAWN - KK	REVISED -
CHECKED - RWI	REVISED -
DATE - 10/19/12	REVISED -

Woodford County
Highway Department

Township Schedule

SCALE: SHEET NO. 05 OF 18 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00016-00-50	Woodford	18	05
	FEDERAL-AID PROJECT		CONTRACT NO.: 89628	